

SUMMARY OF QUANTITIES

CONSTRUCTION CODE 0013

100% STATE

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	BRIDGE		ROADWAY
				LOCATION 1	LOCATION 2	RURAL
				SN 101-0087	SN 071-0022	
50102400	CONCRETE REMOVAL	CU YD	63	16	47	
50300225	CONCRETE STRUCTURES	CU YD	14		14	
50300255	CONCRETE SUPERSTRUCTURE	CU YD	15	11	4	
50301350	SUPERSTRUCTURE CONCRETE (APPROACH SLAB)	CU YD	44	4	40	
50300300	PROTECTIVE COAT	SQ YD	155	43	112	
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	16082	3498	12584	
50800515	BAR SPLICERS	EACH	126	26	100	
52000025	PREFORMED JOINT SEAL, 2"	FOOT	95	50	45	
52000110	PREFORMED JOINT STRIP SEAL	FOOT	95	50	45	
67100100	MOBILIZATION	L SUM	1	0.5	0.5	
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	2	1	1	
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	0.5	0.5	
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	2	1	1	
70106700	TEMPORARY RUMBLE STRIPS	EACH	6	3	3	
70107025	CHANGEABLE MESSAGE SIGN	CAL DA	60	30	30	
70307120	TEMPORARY PAVEMENT MARKING - LINE 4" - TYPE IV TAPE	FOOT	5755	1800	3955	
70307210	TEMPORARY PAVEMENT MARKING - LINE 24" - TYPE IV TAPE	FOOT	48	24	24	



MODEL: Default
 FILE NAME: C:\Users\scott\Desktop\W0 6 64S66 SN 071-0022 and 101-0087\Submittal\12a-6-23-4-23803-05 Leech-SOQ.dgn

Environmental Design International Inc.
 Civil, Survey, Environmental and Construction Inspection Services
 23 W. MONROE STREET, SUITE 1825, CHICAGO, IL 60603
 TEL: (312) 345-1400 FAX: (312) 345-0239 www.ediintl.com

USER NAME = scottw	DESIGNED -	REVISED -
PLOT SCALE = 1/9993" = 1/in.	DRAWN -	REVISED -
PLOT DATE = 12/6/2023	CHECKED -	REVISED -
	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

LOC 1: IL 70 AT SN 101-0087 AND LOC 2: IL 2 /72 AT SN 071-0022
SUMMARY OF QUANTITIES

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
FAS 55 FAP 742	(37BR-2) & (102B-1R-1)	WINNEBAGO, OGLE	30	3
CONTRACT NO. 64S66			ILLINOIS FED. AID PROJECT	

SCALE: N/A SHEET 3 OF 30 SHEETS STA. TO STA.

REV. 2/26/24 REV. 1/17/24 REV. 1/2/24 REV. 12/18/23