

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57	2005-038 I	COOK/WILL	58	4
STA.		TO STA.		
FED. ROAD DIST. NO. 1		ILLINOIS	FED. AID PROJECT	
CONTRACT 60A09				

SOCKETED POST AND CABLE (FOR TL-4 SYSTEM)

STA.	TO	STA.	LENGTH (FT.)
99+00	TO	117+10	1810
117+90	TO	224+20	10630
229+90	TO	258+30	2840
259+30	TO	354+10	9480
355+00	TO	417+65	6265
418+50	TO	476+30	5780
476+90	TO	506+50	2960
507+40	TO	596+30	8890
597+05	TO	775+50	17845
776+35	TO	871+00	9465
877+00	TO	888+50	1150
889+30	TO	900+00	1070
903+75	TO	1006+00	10225
1006+80	TO	1059+40	5260
1060+25	TO	1112+30	5205
1113+20	TO	1135+00	2180
TOTAL LENGTH			101,055

WRGT-RD END TERMINALS (FOR TL-4 SYSTEM)

STA.	EACH
99+00	1
117+10	1
117+90	1
224+20	1
229+90	1
258+30	1
259+30	1
354+10	1
355+00	1
417+65	1
418+50	1
476+30	1
476+90	1
506+50	1
507+40	1
596+30	1
597+05	1
775+50	1
776+35	1
871+00	1
877+00	1
888+50	1
889+30	1
900+00	1
903+75	1
1006+00	1
1006+80	1
1059+40	1
1060+25	1
1112+30	1
1113+20	1
1135+00	1
TOTAL	32

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

**INTERSTATE 57
SCHEDULE OF QUANTITIES**

SCALE: VERT. : NONE
HORIZ. : NONE

DATE: _____ DRAWN BY: HMO
CHECKED BY: _____