

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
5780	2005-056I	WILL	20	2
FED. ROAD DIST. NO. 1	ILLINOIS	HIGHWAY PROJECT		

CONTRACT: 60A44

INDEX OF SHEETS

<u>SHEET NO.</u>	<u>DESCRIPTION</u>
1	TITLE SHEET
2	INDEX OF SHEETS, STATE STANDARDS AND GENERAL NOTES
3	SUMMARY OF QUANTITIES
4	FREEWAY ENTRANCE AND EXIT RAMP CLOUSURE DETAILS
5	TEMPORARY INFORMATION SIGNING
6-20	WEIGH STATION DETAILS

LIST OF STANDARDS

<u>STANDARDS</u>	<u>DESCRIPTION</u>
000001-04	STANDARD SYMBOLS ABBREVIATIONS AND PATTERNS
420701-01	PAVEMENT FABRIC
442101-05	CLASS B PATCHES
702001-05	TRAFFIC CONTROL DEVICES

GENERAL NOTES

BEFORE STARTING ANY EXCAVATION, THE CONTRACTOR SHALL CALL "JULIE" (JOINT UTILITY LOCATION INFORMATION FOR EXCAVATION) AT 800-892-0123 FOR FIELD LOCATIONS OF BURIED ELECTRIC, TELEPHONE & GAS FACILITIES. (48 HOURS NOTIFICATION IS REQUIRED)

ALL ENTRANCES AND EXITS SHALL BE BARRICADED USING TYPE III BARRICADES WITH A ROAD CLOSED SIGN (R11-2) WITH TWO FLASHING YELLOW LIGHT PER BARRICADE. THE TYPE III BARRICADES SHALL BE PAID FOR AT THE CONTRACT PRICE LUMP SUM FOR "TRAFFIC CONTROL AND PROTECTION".

THE CONTRACTOR WILL NOT BE ALLOWED TO SET UP A YARD OR FIELD OFFICE ON STATE PROPERTY WITHOUT WRITTEN PERMISSION FROM THE DEPARTMENT.

IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO VERIFY ALL DIMENSIONS AND CONDITIONS EXISTING IN THE FIELD PRIOR TO CONSTRUCTION AND ORDERING OF MATERIALS.

THE CONTRACTOR SHALL COORDINATE CONSTRUCTION ACTIVITIES WITH UTILITY COMPANIES.

THE CONSTRUCTION MUST BE DONE IN STAGES. THROUGHOUT THE CONSTRUCTION PROCESS, ONE WEIGH STATION WILL BE COMPLETELY CLOSED AT EACH LOCATION.

ALL PAVEMENT PATCHING LOCATIONS WILL BE DETERMINED IN THE FIELD BY THE ENGINEER.

12/19/2005
c:\p\proj\sect\stg\105-406\105-406.dwg

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

**INDEX OF SHEETS,
LIST OF STATE STANDARDS
AND GENERAL NOTES**

SCALE: VERT. NONE
HORIZ.
DATE

DRAWN BY G. LEE
CHECKED BY