

P.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
94	2005-0111	COOK	40	3
FED. ROAD DIST. NO. 1		ILLINOIS	HIGHWAY PROJECT	
CONTRACT NO. 62929				

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT		OUTSIDE SHOULDERS				
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	80	80				
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	1	1				
67100100	MOBILIZATION	L SUM	1	1				
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	147000	147000				
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	49000	49000				
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	147000	147000				
78300100	PAVEMENT MARKING REMOVAL	SQ FT	49000	49000				
X7011015	TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS)	L SUM	1	1				
X7013820	TRAFFIC CONTROL SURVEILLANCE, EXPRESSWAYS	CAL DA	15	15				
XZ186500	ASPHALTIC EMULSION SLURRY SEAL	SQ YD	196000	196000				
X0325223	FIBER ASPHALT	POUND	1340	1340				

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT						

* SPECIALITY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 FAI 94/I-94 (INTERSTATE 94)
 LAWRENCE AVE TO LAKE-COOK RD
 SUMMARY OF QUANTITIES

12/13/2005 09:27:01 AM C:\PLOT\10380960.DWG