

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
309	16R-2	WHITESIDE	57	22
STA.		TO STA.		
FED. ROAD DIST. NO. 2		ILLINOIS		FED. AID PROJECT

PAY CODE		50104400	50105220	60500040	60500060	XX146400				
STORM SEWER REMOVAL SCHEDULE										
LOCATION		CONCRETE HEADWALL REMOVAL	PIPE CULVERT REMOVAL	REMOVING MANHOLES	REMOVING INLETS	STORM SEWER REMOVAL				
		EACH	FOOT	EACH	EACH	12"	15"	24"	30"	
		FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	
US RTE 30 - URBAN										
STA. 1123+89.12	31.48 FT	LT								
STA. 1123+89.12	31.48 FT	LT	TO	STA. 1123+94.52	19.69 FT	LT			12.97	
STA. 1123+94.52	19.69 FT	LT								
STA. 1123+94.52	19.69 FT	LT	TO	STA. 1123+97.24	19.31 FT	RT			39.09	
STA. 1123+96.83	30.00 FT	RT								
STA. 1123+96.83	30.00 FT	RT	TO	STA. 1123+97.24	19.31 FT	RT			10.70	
STA. 1124+00.91	30.95 FT	LT	TO	STA. 1125+04.01	15.89 FT	LT		104.14		
STA. 1125+04.01	15.89 FT	LT								
STA. 1126+94.15	46.75 FT	LT	TO	STA. 1127+18.19	47.41 FT	LT			34.02	
STA. 1127+18.19	47.41 FT	LT								
STA. 1127+18.19	47.41 FT	LT	TO	STA. 1127+22.23	41.75 FT	LT		7.01		
STA. 1127+22.23	41.75 FT	LT								
STA. 1127+22.23	41.75 FT	LT	TO	STA. 1127+56.37	41.69 FT	LT		34.01		
STA. 1127+56.37	41.69 FT	LT								
STA. 1127+56.37	41.69 FT	LT	TO	STA. 1127+83.84	22.74 FT	LT		33.36		
STA. 1127+83.84	22.74 FT	LT								
STA. 1130+84.56	33.57 FT	LT								
STA. 1130+84.56	33.57 FT	LT	TO	STA. 1131+23.66	33.23 FT	LT		39.07		
STA. 1131+23.66	33.23 FT	LT								
STA. 1131+23.66	33.23 FT	LT	TO	STA. 1131+56.00	15.47 FT	LT			36.90	
STA. 1131+56.00	15.47 FT	LT								
STA. 1131+56.00	15.47 FT	LT	TO	STA. 1131+56.00	15.47 FT	LT			54.47	
STA. 1131+56.00	15.47 FT	LT								
SAWYER ROAD										
STA. 8+26.99	23.02 FT	RT	TO	STA. 8+79.73	23.03 FT	RT				
SUBTOTAL - URBAN		2		53	5	5	113.45	104.14	125.39	62.76
TOTAL - URBAN		2		53	5	5	114	105	126	63
TOTAL		2		53	5	5		408		

PAY CODE		70400100	70400200	20030260	20030330
TEMPORARY CONCRETE BARRIER SCHEDULE					
LOCATION		TEMPORARY CONCRETE BARRIER	RELOCATE TEMPORARY CONCRETE BARRIER	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3	IMPACT ATTENUATORS, RELOCATE (FULLY REDIRECTIVE), TEST LEVEL 3
		FOOT	FOOT	EACH	EACH
ROUTE 30 - RURAL					
STA. 1157+16.10	TO	STA. 1159+00.25	RT	5	
STA. 1157+22.00	TO	STA. 1159+06.25		4	186.41
SUBTOTAL - RURAL		381	187	2	2
TOTAL		380	190	2	2

PAY CODE		66400560		
FENCE SCHEDULE				
LOCATION		CHAIN LINK FENCE, 6' (SPECIAL)		
		FOOT		
US RTE 30 - URBAN				
STA. 1127+90.75	TO	STA. 1130+71.01	LT	283.37
STA. 1131+71.68	TO	STA. 1133+44.95	LT	173.34
SUBTOTAL - URBAN		457		
TOTAL		457		

PAY CODE		20101100	
TREE TRUNK PROTECTION SCHEDULE			
LOCATION		TREE TRUNK PROTECTION	
		EACH	
US RTE 30 - URBAN			
STA. 1118+82.20	42.13	LT	1
STA. 1122+26.68	51.04	RT	1
STA. 1122+56.35	52.83	RT	1
STA. 1128+51.65	59.16	RT	1
STA. 1129+86.94	63.91	LT	1
STA. 1130+05.97	63.93	LT	1
STA. 1138+12.25	79.44	LT	1
STA. 1139+67.43	86.89	LT	1
SCENIC STREET			
STA. 15+60.14	23.71	LT	1
SAWYER ROAD			
STA. 8+82.72	53.16	RT	1
SUBTOTAL - URBAN		10	
US RTE 30 - RURAL			
STA. 1159+32.00	65.00	RT	1
STA. 1159+83.00	65.00	RT	1
STA. 1166+48.83	50.45	RT	1
SUBTOTAL - RURAL		3	
TOTAL		13	

PAY CODE		78300100	78300200	
PAVEMENT MARKING REMOVAL SCHEDULE				
LOCATION		PAVEMENT MARKING REMOVAL	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	
		SQ FT	EACH	
US RTE 30 - URBAN				
STA. 1108+81.68	TO	STA. 1110+37.04	RT	14
STA. 1108+81.68	TO	STA. 1114+01.68		721.02
STA. 1122+50.00	TO	STA. 1126+00.00	RT	116.55
STA. 1126+00.00	TO	STA. 1132+00.00	RT	183.15
STA. 1132+00.00	TO	STA. 1138+00.00	RT	199.80
STA. 1138+00.00	TO	STA. 1144+00.00	RT	199.80
STA. 1144+00.00	TO	STA. 1150+00.00	RT	199.80
STA. 1150+00.00	TO	STA. 1156+00.00	RT	199.80
STA. 1156+00.00	TO	STA. 1157+00.00	RT	33.30
SUBTOTAL - URBAN		1,854	14	
US RTE 30 - RURAL				
STA. 1157+00.00	TO	STA. 1162+00.00	RT	166.50
STA. 1162+00.00	TO	STA. 1168+00.00	RT	199.80
STA. 1168+00.00	TO	STA. 1174+30.00	RT	199.80
STA. 1174+30.00	TO	STA. 1178+30.00	RT	133.20
STA. 1174+30.00	TO	STA. 1178+30.00	LT	133.20
STA. 1174+30.00	TO	STA. 1178+30.00	LT	33.30
SUBTOTAL - RURAL		866	0	
TOTAL		2,720	14	

PAY CODE		44004300	
PAVEMENT BREAKING SCHEDULE			
LOCATION		PAVEMENT BREAKING	
		SQ YD	
US RTE 30 - URBAN			
STA. 1156+00.00	TO	STA. 1157+00.00	427.08
SUBTOTAL - URBAN		428	
US RTE 30 - RURAL			
STA. 1157+00.00	TO	STA. 1157+87.00	246.78
STA. 1158+43.00	TO	STA. 1162+00.00	1,017.24
STA. 1162+00.00	TO	STA. 1168+00.00	1,683.16
SUBTOTAL - RURAL		2,948	
TOTAL		3,376	

PAY CODE		XZ127900		
RETAINING WALL REMOVAL SCHEDULE				
LOCATION		RETAINING WALL REMOVAL		
		FOOT		
US RTE 30 - URBAN				
STA. 1117+70.89	TO	STA. 1117+71.54	LT	8.38
STA. 1117+86.04	TO	STA. 1117+90.38	LT	9.74
SUBTOTAL - URBAN		19		
TOTAL		19		

PAY CODE		63000000	63100045		
GUARDRAIL SCHEDULE					
LOCATION		STEEL PLATE BEAM GUARD RAIL, TYPE A	TRAFFIC BARRIER TERMINAL, TYPE 2		
		FOOT	EACH		
US RTE 30 - URBAN					
STA. 1128+23.15	LT	TO	STA. 1128+37.43	LT	1
STA. 1128+37.43	LT	TO	STA. 1128+44.88	LT	7.44
STA. 1128+44.88	LT	TO	STA. 1128+59.17	LT	1
SUBTOTAL - URBAN		12.5	2		
TOTAL		12.5	2		

PAY CODE		Z0049800
RELOCATE EXISTING SURVEY MARKERS SCHEDULE		
LOCATION		RELOCATE EXISTING SURVEY MARKERS
		EACH
US ROUTE 30 - RURAL		
LOCATION 1		60
SUBTOTAL - RURAL		60
TOTAL		60

PAY CODE		44000300			
CURB REMOVAL SCHEDULE					
LOCATION		CURB REMOVAL			
		FOOT			
US RTE 30 - URBAN					
STA. 1132+75.49	RT	TO	STA. 1132+77.45	RT	24.0
SUBTOTAL - URBAN		24			
TOTAL		24			

PAY CODE		Z0013300		
CONCRETE REMOVAL (SPECIAL) - 1.25' WIDE SCHEDULE				
LOCATION		CONCRETE REMOVAL (SPECIAL)		
		SQ YD		
US RTE 30 - URBAN				
STA. 1117+12.34	TO	STA. 1118+56.05	RT	19.97
SUBTOTAL - URBAN		20		
TOTAL		20		

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		SCHEDULE OF QUANTITIES FAP ROUTE 309 (US 30) SECTION 16R-2, EAST CONTRACT FROM 0.2 MILE EAST OF JACKSON ST. TO FRENCH CREEK WHITESIDE COUNTY
		SCALE: N.T.S.
		DATE: 09/01/05
		DRAWN BY: CAM
		CHECKED BY: RYD

REVISED
2-23-06