

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
642	(10BR-31D)	JODAVIESS	45	2
STA.	11BR-8 TO STA.			
FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT			

# SUMMARY OF QUANTITIES

CODE NUMBER	PAY ITEM	UNIT	TOTAL QUANTITY	BR FUNDS		STP FUNDS
				X080-2A 100% STATE	SFTY-3N 100% STATE	F
				BHF		1/100 STATE
						SFTY-2A EXIST. SN# 043-0040
20200600	EXCAVATING & GRADING EXISTING SHOULDERS	UNIT	1	1		
20400800	FURNISHED EXCAVATION	CU YD	75	75		
25100630	EROSION CONTROL BLANKET	SQ YD	1114	1114		
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	150	150		
28000400	PERIMETER EROSION BARRIER	FOOT	950	950		
X4006765	LEVELING BINDER (MACHINE METHOD) SUPERPAVE N50	TON	114	114		
44000007	BITUMINOUS CONCRETE SURFACE REMOVAL 2"	SQ YD	282	158		124
44001205	BITUMINOUS CONCRETE SURFACE REMOVAL COMPLETE	SQ YD	555			555
48101200	AGGREGATE SHOULDERS, TYPE B	TON	190	190		
48200300	BITUMINOUS SHOULDERS 5"	SQ YD	366	366		
50101500	REMOVAL OF EXISTING SUPERSTRUCTURES	EACH	1	1		
50102400	CONCRETE REMOVAL	CU YD	20.7	12.6		8.1
50300100	FLOOR DRAINS	EACH	8.0			8.0
50300225	CONCRETE STRUCTURES	CU YD	11.7	5.4		6.3
50300255	CONCRETE SUPERSTRUCTURE	CU YD	2.7			2.7
50300260	BRIDGE DECK GROOVING	SQ YD	924	409		515
50300300	PROTECTIVE COAT	SQ YD	1013	447		566
50300530	FLOOR DRAIN EXTENSION	EACH	8			8
50301250	FORMED CONCRETE REPAIR (DEPTH GREATER THAN 5")	SQ FT	21			21
50400305	PRECAST PRESTRESSED CONCRETE DECK BEAMS (17" DEPTH)	SQ. FT.	3852	3852		
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	14530	6400		8130
50901005	STEEL BRIDGE RAIL, TYPE SM	FOOT	214	214		
51500100	NAME PLATES	EACH	1	1		
542D0220	PIPE CULVERTS, CLASSD, TYPE 1 15"	FOOT	50	50		
54213450	END SECTIONS 15"	EACH	1	1		
* 63000005	STEEL PLATE BEAM GUARDRAIL, TYPE B	FOOT	402	402		
* 63100087	TRAFFIC BARRIER TERMINAL, TYPE 6A	EACH	4	4		

\* SPECIALTY ITEMS

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		SCALE: VERT. HORIZ. DATE DRAWN BY CHECKED BY

PLOT DATE = Fri Dec 30 09:22:44 2005  
 PLOT SCALE = 50.0000  
 USER NAME = rjgwr-1