

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
642	108R-3D	JODAVIESS	45	8
STA. 118R-8		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

# SCHEDULE OF QUANTITIES

**20200600 EXCAVATING & GRADING EXISTING SHOULDERS**

UNIT	LOCATION		
1	18+12 - 23+62	LT & RT	
1	TOTAL		

**20400800 FURNISHED EXCAVATION**

CU YD	LOCATION		
75	18+12 - 23+62	LT & RT	
75	TOTAL		

**25100630 EROSION CONTROL BLANKET**

SQ YD	LOCATION		
444	18+04 - 20+21	LT & RT	
670	21+28 - 23+86	LT & RT	
1114	TOTAL		

**28000250 TEMPORARY EROSION CONTROL**

POUND	LOCATION		
70	18+04 - 20+21	LT & RT	
80	21+28 - 23+86	LT & RT	
150	TOTAL		

**28000400 PERIMETER EROSION BARRIER**

EQFT	LOCATION		
211	18+12 - 20+21	LT	
230	18+04 - 20+21	RT	
275	21+28 - 23+86	LT	
234	21+27 - 23+62	RT	
950	TOTAL		

**40600530 LEVELING BINDER (MACHINE METHOD) MIX C. TYPE 1, N50**

TON	LOCATION		
53	18+42 - 20+21		
61	21+28 - 23+40		
114	TOTAL		

**44000007 BITUMINOUS CONCRETE SURFACE REMOVAL 2"**

SQ YD	LOCATION		
79	18+12 - 18+42		
80	23+32 - 23+62		
61	317+37 - 317+63		
62	319+09 - 319+35		
282	TOTAL		

**48101200 AGGREGATE SHOULDERS, TYPE B**

TON	LOCATION		
50	18+04 - 20+21	RT	
50	18+51 - 20+21	LT	
45	21+28 - 22+90	RT	
45	21+28 - 23+86	LT	
190	TOTAL		

**48200300 BITUMINOUS SHOULDERS 5"**

SQ YD	LOCATION		
86	18+12 - 20+06	RT	
97	21+44 - 23+62	RT	
86	18+12 - 20+06	LT	
97	21+44 - 23+62	LT	
366	TOTAL		

**54200220 PIPE CULVERTS, CLASS D, TYPE 1 15'**

EQFT	LOCATION		
50	18+15 - 18+65	RT	
50	TOTAL		

**54213450 END SECTIONS 15"**

EACH	LOCATION		
1	18+65	RT	
1	TOTAL		

**63000005 STEEL PLATE BEAM GUARDRAIL, TYPE B**

EQFT	LOCATION		
63	19+25 - 19+88	LT	
126	18+62 - 19+88	RT	
150	21+62 - 23+12	LT	
63	21+62 - 22+25	RT	
402	TOTAL		

**63100087 TRAFFIC BARRIER TERMINAL, TYPE 6A**

EACH	LOCATION		
1	20+21	LT	
1	21+28	LT	
1	20+21	RT	
1	21+28	RT	
4	TOTAL		

**63100167 TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)**

EACH	LOCATION		
1	18+75 - 19+25	LT	
1	18+12 - 18+62	RT	
1	23+12 - 23+62	LT	
1	22+25 - 22+75	RT	
4	TOTAL		

PLOT DATE = Fri Dec 30 09:05:18 2005  
 PLOT SCALE = 500000 / IN.  
 USER NAME = rjgport1

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCALE: VERT. \_\_\_\_\_  
 DATE \_\_\_\_\_

DRAWN BY \_\_\_\_\_  
 CHECKED BY \_\_\_\_\_