CONTRACT NO. 64B27

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
642	(10BR-3)D	JODAVIESS	45	9
STA.	11BR-8	TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

SCHEDULE OF QUANTITIES

63200310 GUARDRAIL REMOVAL

FOOT	LOCATION		
148	18+73	- 20+21	LT
211	21+28	- 23+39	LT
210	18+11	- 20+21	RT
148	21+28	- 22+76	RT
717	TOTAL		

63500105 DELINEATORS

EACH	LOCATION	
1	18+75	LT
1	18+12	RT
1	23+62	LT
1	22+75	RT
4	TOTAL	

70300200 TEMPORARY PAVEMENT MARKING

FOOT	LOCATION			
638	16+62	- 23+00	YELLOW	STAGE 1
511	17+89	- 23+00	WHITE	STAGE 1
638	16+62	- 23+00	YELLOW	STAGE 2
526	17+74	- 23+00	WHITE	STAGE 2
413	315+87	- 320+00	YELLOW	STAGE 1
413	315+87	- 320+00	WHITE	STAGE 1
413	315+87	- 320+00	YELLOW	STAGE 2
413	315+87	- 320+00	WHITE	STAGE 2
3965	TOTAL			

70301000 WORK ZONE PAVEMENT MARKING REMOVAL

SQ FT	LOCATION		
16	18+14	- 18+88	STAGE 1 CL
171	18+14	- 23+34	STAGE 1 WHITE RT
24	22+62	- 23+34	STAGE 1 CL
171	18+14	- 23+34	STAGE 2 WHITE LT
382	TOTAL		

70400100 TEMPORARY CONCRETE BARRIER

FOOT	LOCATION	
480	18+35	- 23+14
480	TOTAL	

70400200 RELOCATE TEMPORARY CONCRETE BARRIER

FOOT	LOCATION	
480	18+35	- 23+14
480	TOTAL	

78001110 PAINT PAVEMENT MARKING LINE 4"

FOOT	LOCATION		
1100	18+12	- 23+62	WHITE EDGELINES - 2 COATS
1100	18+12	- 23+62	WHITE EDGELINES - 2 COATS
280	18+12	- 23+62	SKIP DASH YELLOW - 2 COATS
436	317+27	- 319+45	WHITE EDGELINES - 2 COATS
436	317+27	- 319+45	WHITE EDGELINES - 2 COATS
110	317+27	- 319+45	SKIP DASH YELLOW - 2 COATS
3462	TOTAL		

78100100 RAISED REFLECTIVE MARKER

EACH	LOCATION	
6	18+12	- 23+62
6	TOTAL	

78200410 GUARDRAIL MARKERS, TYPE A

EACH	LOCATION		
2	19+25	- 19+88	LT
5	18+62	- 19+88	RT
6	21+62	- 23+12	LT
2	21+62	- 22+25	RT
15	TOTAL		

78201000 TERMINAL MARKER - DIRECT APPLIED

EACH	LOCATION	
1	18+75	LT
1	18+12	RT
1	23+62	LT
1	22+75	RT
4	TOTAL	

78300200 RAISED REFLECTIVE PAVEMENT MARKER REMOVAL

EACH	LOCATION	
6	18+12	- 23+62
6	TOTAL	

X0712400 TEMPORARY PAVEMENT

SQ YD	LOCATION		
10	317+28	- 317+47	RT
14	319+33	- 319+63	RT
24	TOTAL		

X4066414 BITUMINOUS CONCRETE SURFACE COARSE, SUPERPAVE, MIX C, N50

TON	LOCATION	
9	18+12	- 18+42
9	23+32	- 23+62
40	18+12	- 20+21
46	21+28	- 23+32
7	317+37	- 317+63
7	319+09	- 319+35
118	TOTAL	

Z0030250 IMPACT ATENUATORS, TEMPORARY (NON -RE-DIRECTIVE), TEST LEVEL3

EACH	LOCATION	
1	18+35	LT
1	23+14	LT
2	TOTAL	

Z0030350 IMPACT ATTENUATORS, RELOCATE (NON -RE-DIRECTIVE), TEST LEVEL 3

EACH	LOCATION	
1	18+35	RT
1	23+14	RT
2	TOTAL	

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCALE: VERT. HORIZ.

DATE

DRAWN BY

CHECKED BY

PLOT DATE = Fri Dec 30 07:02:19 2005
FILE NAME = c:\projects\p22940B5\d9940sv.dgn
PLOT SCALE = 10.0000 / IN.
USER NAME = rayfoul