

SUMMARY OF QUANTITIES

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1324	38 BR-1	IROQUOIS	29	3
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

PAY CODE NUMBER	PAY ITEM	UNIT	TOTAL	ROADWAY	BRIDGE
				80% FED 20% ST X080-2A	80% FED 20% ST X080-2A
28000900	FENCE (EROSION CONTROL)	FOOT	900	900	
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	60	60	
40600980	BITUMINOUS SURFACE REMOVAL-BUTT JOINT	SQ. YD.	594	594	
40600990	TEMPORARY RAMP	SQ. YD.	110	110	
44000300	CURB REMOVAL	FOOT	48	48	
48101200	AGGREGATE SHOULDERS, TYPE B	TON	40	40	
50101500	REMOVAL OF EXISTING SUPERSTRUCTURES	EACH	1		1
50102400	CONCRETE REMOVAL	CU. YD.	4.4		4.4
50300225	CONCRETE STRUCTURES	CU. YD.	5.7		5.7
50300260	BRIDGE DECK GROOVING	SQ. YD.	417		417
50300300	PROTECTIVE COAT	SQ. YD.	445		445
50400305	PRECAST PRESTRESSED CONCRETE DECK BEAMS (17" DEPTH)	SQ. FT.	4000		4000
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	6520		6520
50901005	STEEL BRIDGE RAIL, TYPE SM	FOOT	256		256
51500100	NAME PLATES	EACH	1		1
63000000	STEEL PLATE BEAM GUARDRAIL, TYPE A	FOOT	100	100	
63100087	TRAFFIC BARRIER TERMINAL, TYPE 6A	EACH	4	4	
63200310	GUARDRAIL REMOVAL	FOOT	150	150	
63304705	TRAFFIC BARRIER TERMINAL REMOVAL, TYPE 5A	EACH	4	4	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL. MO.	3	3	
67100100	MOBILIZATION	L. SUM	1	1	
70102550	TRAFFIC CONTROL AND PROTECTION FOR TEMPORARY DETOURS	EACH	1	1	
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL. DAY	45	45	
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	33	33	
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	660	660	
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	90	90	
70301000	WORKZONE PAVEMENT MARKING REMOVAL	SQ. FT.	263	263	

PAY CODE NUMBER	PAY ITEM	UNIT	TOTAL	ROADWAY	BRIDGE
				80% FED 20% ST X080-2A	80% FED 20% ST X080-2A
78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	660	660	
78001130	PAINT PAVEMENT MARKING - LINE 6"	FOOT	90	90	
78100100	RAISED REFLECTIVE PAVEMENT MARKERS	EACH	4	4	
78200410	GUARDRAIL MARKERS, TYPE A	EACH	4	4	
78300200	RAISED REFLECTIVE PAVEMENT MARKING REMOVAL	EACH	3	3	
X4066414	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "C", N50	TON	56	56	
X4066765	LEVELING BINDER (MACHINE METHOD), SUPERPAVE N50	TON	32	32	
X5030305	CONCRETE WEARING SURFACE, 5"	SQ. YD.	445		445

* SPECIALTY ITEM

PLOT DATE = 12/05/2005
 FILE NAME = J:\03236\SUM\03236_SUM.dgn
 PLOT SCALE = 50.00000 / IN.
 REFERENCE = REF
 OPERATOR = rjpb

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

FAS 1324 (OLD US RTE. 45)
 SECTION 38 BR-1
 IROQUOIS COUNTY

SCALE: VERT. _____
 HORIZ. _____

DATE _____

DRAWN BY: HEBERLING
 CHECKED BY: BOIT

GREENE & BRADFORD, INC.
 OF SPRINGFIELD

COMPUTER FILE NO.
 03236_SUM

PROJECT 03236 W010
 12/8/05-MML