

# SUMMARY OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
785	1331-1	MADISON	29	3
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		1000-1A 90% FED 10% STATE		
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	90	90		
20200100	EARTH EXCAVATION	CU YD	410	410		
25000200	SEEDING, CLASS 2	ACRE	0.4	0.4		
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	34	34		
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	34	34		
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	34	34		
25100115	MULCH, METHOD 2	ACRE	0.4	0.4		
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	43	43		
28000300	TEMPORARY DITCH CHECKS	EACH	28	28		
28000500	INLET AND PIPE PROTECTION	EACH	3	3		
35101100	AGGREGATE BASE COURSE, TYPE A 12"	SQ YD	2526	2526		
35102000	AGGREGATE BASE COURSE, TYPE B 8"	SQ YD	28	28		
40200900	AGGREGATE SURFACE COURSE, TYPE B	CU YD	10	10		
40600980	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	SQ YD	48	48		
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SQ YD	53	53		
40600990	TEMPORARY RAMP	SQ YD	42	42		
40800020	BITUMINOUS MATERIALS (PRIME COAT)	TON	1.6	1.6		
40800030	AGGREGATE (PRIME COAT)	TON	7.2	7.2		
40800040	INCIDENTAL BITUMINOUS SURFACING	TON	5	5		
44000003	BITUMINOUS SURFACE REMOVAL 3/4"	SQ YD	4087	4087		
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	42	42		
44003100	MEDIAN REMOVAL	SQ FT	138	138		
44004250	PAVED SHOULDER REMOVAL	SQ YD	1250	1250		
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	2243	2243		
48100500	AGGREGATE SHOULDERS, TYPE A 6"	SQ YD	644	644		
48202600	BITUMINOUS SHOULDERS SUPERPAVE 8"	SQ YD	1013	1013		
50104400	CONCRETE HEADWALL REMOVAL	EACH	2	2		
50105220	PIPE CULVERT REMOVAL	FOOT	25	25		
54213660	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15"	EACH	2	2		
542A0220	PIPE CULVERTS, CLASS A, TYPE 1 15"	FOOT	25	25		
60603500	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.06	FOOT	19	19		
60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SQ FT	31	31		
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	2	2		
67100100	MOBILIZATION	L SUM	1	1		
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1		

SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		1000-1A 90% FED 10% STATE		
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1		
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	1		
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	11	11		
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	860	860		
70300210	TEMPORARY PAVEMENT MARKING, LETTERS AND SYMBOLS	SQ FT	57	57		
70300220	TEMPORARY PAVEMENT MARKING LINE 4"	FOOT	6464	6464		
70300250	TEMPORARY PAVEMENT MARKING LINE 8"	FOOT	154	154		
70300260	TEMPORARY PAVEMENT MARKING LINE 12"	FOOT	1054	1054		
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	215	215		
* 72400600	RELOCATE SIGN PANEL ASSEMBLY - TYPE B	EACH	31	31		
* 72400710	RELOCATE SIGN PANEL - TYPE 1	SQ FT	18	18		
* 72400720	RELOCATE SIGN PANEL - TYPE 2	SQ FT	24.5	24.5		
* 73000100	WOOD SIGN SUPPORT	FOOT	114	114		
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	57	57		
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	6464	6464		
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	154	154		
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	1054	1054		
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	61	61		
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	14	14		
X3550810	BITUMINOUS BASE COURSE SUPERPAVE 11 1/2"	SQ YD	1763	1763		
X4066426	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N70	TON	421	421		
X4066770	LEVELING BINDER (MACHINE METHOD), SUPERPAVE N70	TON	211	211		

\* SPECIALTY ITEMS

Rev.