

FAU. RFL.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2955	02-00049-00-PV	COOK	45	4
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

Contract 83819

SUMMARY OF QUANTITIES					PAVEMENT	SIDEWALKS	MARKINGS	SIGNS	LANDSCAPE	SIGNALS	TRAINING		
S.P. CODE NO.	PAY ITEM	UNIT	QUAN	CONSTRUCTION TYPE CODE									
				I000	SFTY-1B	SFTY-1D	Y002-1C	Y003	Y031	Y080			
* 20200410	EARTH EXCAVATION (SPECIAL)	CU YD	8097	8097									
* 20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	100	100									
20201550	SUB-BASE GRANULAR MATERIAL, TYPE B	CU YD	1171	1171									
* 20700420	POROUS GRANULAR EMBANKMENT, SUBGRADE	CU YD	100	100									
20800150	TRENCH BACKFILL	CU YD	3454	3454									
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	10518						10518				
* 21400100	GRADING AND SHAPING DITCHES	FOOT	300	300									
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	130						130				
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	130						130				
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	130						130				
25200110	SODDING, SALT TOLERANT	SQ YD	10518						10518				
28000300	TEMPORARY DITCH CHECKS	EACH	1	1									
28000400	PERIMETER EROSION BARRIER	FOOT	1370	1370									
* 28000510	INLET FILTERS	EACH	67	67									
28100107	STONE RIPRAP, CLASS A4	SQ YD	12	12									
28200200	FILTER FABRIC	SQ YD	12	12									
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	428	428									
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	1572	1572									
40600980	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	SQ YD	379	379									
42001300	PROTECTIVE COAT	SQ YD	4259	4259									
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	22858		22858								
44000100	PAVEMENT REMOVAL	SQ YD	9233	9233									
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	1909	1909									
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	577	577									
44000600	SIDEWALK REMOVAL	SQ FT	4389	4389									
* 44212899	PAVEMENT PATCHING (FULL DEPTH)	SQ YD	638	638									
* 50104400	CONCRETE HEADWALL REMOVAL	EACH	1	1									
* 50105200	REMOVE EXISTING CULVERTS	EACH	43	43									
55019500	STORM SEWERS, TYPE 1, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS IV 12"	FOOT	102	102									
55020300	STORM SEWERS, TYPE 1, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III 36"	FOOT	374	374									
55021600	STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III 12"	FOOT	1112	1112									
55021700	STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III 15"	FOOT	479	479									
55021800	STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III 18"	FOOT	156	156									
55022000	STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III 24"	FOOT	480	480									
55022200	STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III 30"	FOOT	413	413									
55022400	STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III 36"	FOOT	537	537									
55024100	STORM SEWERS, TYPE 3, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS IV 24"	FOOT	335	335									
55024300	STORM SEWERS, TYPE 3, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS IV 30"	FOOT	475	475									
55100500	STORM SEWER REMOVAL 12"	FOOT	165	165									
55100700	STORM SEWER REMOVAL 15"	FOOT	403	403									
55101200	STORM SEWER REMOVAL 24"	FOOT	495	495									
△ * 56103000	DUCTILE IRON WATER MAIN 6"	FOOT	95	95									
△ * 56103100	DUCTILE IRON WATER MAIN 8"	FOOT	60	60									
△ * 56103300	DUCTILE IRON WATER MAIN 12"	FOOT	335	335									

* - INDICATES SPECIAL PROVISIONS

△ - SPECIALTY ITEM

ROBINSON ENGINEERING, LTD. CONSULTING REGISTERED PROFESSIONAL ENGINEERS AND PROFESSIONAL LAND SURVEYORS 17000 SOUTH PARK AVENUE SOUTH HOLLAND, ILLINOIS 60473 (708) 381-6700		REVISIONS <table border="1"> <tr> <th>No.</th> <th>Date</th> <th>Remarks</th> </tr> <tr> <td>1</td> <td>8-23-04</td> <td>PS</td> </tr> <tr> <td>2</td> <td>9-7-05</td> <td>REL</td> </tr> </table>		No.	Date	Remarks	1	8-23-04	PS	2	9-7-05	REL
No.	Date	Remarks										
1	8-23-04	PS										
2	9-7-05	REL										
© COPYRIGHT 2004 ILLINOIS DESIGN FIRM REGISTRATION NO. 184001128												
OAK PARK AVENUE RECONSTRUCTION 115TH STREET TO 111TH STREET SUMMARY OF QUANTITIES												
WORTH,		ILLINOIS										
Drawn by: EC	Date: 3/31/04											
Checked by: JMN	Scale: NA											
Sheet of	Project No. 02-162											