FAU. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO
2955	02-00049-00-PV	COOK	45	18
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

Contract 83819

PIPE SCHEDULE

LOCATION											SS T1 RCP		SS T2 RCP						SS T3 RCP		SS WMR DIP				CU. YDS. TRENCH BACKFILL
PIPE NO.	STATION	OFFSET			TO	STRC NO.	STATION	OFFSET			12	36	12	15	18	24	30	36	24	30	12	24	30	36	
1	31+23	15	FT	RT	TO	5	31+49	7.5	FT	RT	16										10				5.04
2	31+11	43.0	FT	RT	TO	3	31+49	23.0	FT	RT			25.0								18.0				2.6
3	31+49	23.0	FT	RT	TO	5	31+49	7.5	FT	RT			5.5								10.0				9.8
4	31+49	25.9	FT	LT	TO	5	31+49	7.5	FT	RT			18.4												4.7
5	31+49	7.5	FT	RT	TO	10	30+25	7.5	FT	RT			124.0												126.1
6	30+25	21.0	FT	LT	TO	7	30+25	13.0	FT	LT			4.0												0.9
7	30+25	13.0	FT	LT	TO	10	30+25	7.5	FT	RT			5.5												4.2
8	30+65	43.0	FT	RT	TO	9	30+25	23.0	FT	RT			27.0								18.0				3.5
9	30+25	23.0	FT	RT	TO	10	30+25	7.5	FT	RT			5.5								10.0				11.8
10	30+25	7.5	FT	RT	TO	15	28+70	7.5	FT	RT				155.0											182.4
12	28+70	21.0	FT	LT	TO	13	28+70	13.0	FT	LT			4.0												0.8
13	28+70	13.0	FT	LT	TO	15	28+70	7.5	FT	RT			5.5												4.0
14	28+70	23.0	FT	RT	TO	15	28+70	7.5	FT	RT			5.5								10.0				3.7
15	28+70	7.5	FT	RT	TO	20	27+68	21.6	FT	RT					102.7										122.5
17	28+12	23.0	FT	RT	TO	20	27+68	21.6	FT	RT			26.0												8.7
18A	27+68	73.0	FT	LT	TO	18	27+68	21.6	FT	LT	51.0														6.7
18	27+68	21.6	FT	LT	TO	20	27+68	21.6	FT	RT			43.2												11.1
19	27+68	50.0	FT	RT	TO	20	27+68	21.6	FT	RT			28.4												3.9
20A	27+32	264.0	FT	LT	TO	20	27+68	21.6	FT	RT				289.0											23.9
20	27+68	21.6	FT	RT	TO	21	27+15	24.5	FT	RT					53.4										54.4
21	27+15	24.5	FT	RT	TO	25	25+61	24.5	FT	RT						154.1									72.7
23	25+61	17.0	FT	LT	TO	24	25+61	17.0	FT	RT			34.0												8.0
24	25+61	17.0	FT	RT	TO	25	25+61	24.5	FT	RT			7.5												1.4
25	25+61	24.5	FT	RT	TO	30	23+50	24.5	FT	RT						210.9									93.5
26	24+32	52.0	FT	LT	TO	27	23+97	52.0	FT	LT	35.0														4.6
27	23+97	52.0	FT	LT	TO	28	23+93	23.6	FT	LT			28.6												3.9
28	23+93	23.6	FT	LT	TO	29	23+72	17.0	FT	RT			45.9												16.6
29	23+72	17.0	FT	RT	TO	30	23+50	24.5	FT	RT			23.2												13.8
30	23+50	24.5	FT	RT	TO	35	22+35	24.5	FT	RT						115.0									42.5
33	22+35	17.0	FT	LT	TO	34	22+35	17.0	FT	RT			34.0												8.7
34	22+35	17.0	FT	RT	TO	35	22+35	24.5	FT	RT			7.5												2.2
35	22+35	24.5	FT	RT	TO	40	20+58	24.5	FT	RT									177.0						193.1
38	20+57	23.6	FT	LT	TO	40	20+58	24.5	FT	RT			48.1												13.4
40	20+58	24.5	FT	RT	TO	45	19+00	24.5	FT	RT									158.0						125.9
43	19+00	17.0	FT	LT	TO	44	19+00	17.0	FT	RT			34.0												8.7
44	19+00	17.0	FT	RT	TO	45	19+00	24.5	FT	RT			7.5												2.7
45	19+00	24.5	FT	RT	TO	50	18+00	24.5	FT	RT										100.0					102.2
46	17+25	84.0	FT	LT	TO	47	17+61	50.0	FT	LT			49.9												6.8
47	17+61	50.0	FT	LT	TO	48	17+85	17.0	FT	LT			40.8												10.3
48	17+85	17.0	FT	LT	TO	49	17+85	17.0	FT	RT			34.0												45.5
49	17+85	17.0	FT	RT	TO	50	18+00	24.5	FT	RT															16.9
50	18+00	24.5	FT	RT	TO	55	16+20	24.5	FT	RT										180.0					288.5
53	16+20	17.0	FT	LT	TO	54	16+20	17.0	FT	RT			34.0												9.5
54	16+20	17.0	FT	RT	TO	55	16+20	24.5	FT	RT			7.5												2.4
55	16+20	24.5	FT	RT	TO	60	14+25	24.5	FT	RT										195.0					171.8
57	14+26	23.2	FT	LT	TO	60	14+25	24.5	FT	RT			47.7												13.3
58	14+23	45.0	FT	RT	TO	60	14+25	24.5	FT	RT			20.6												5.7
60	14+25	24.5	FT	RT	TO	65	13+50	24.5	FT	RT							75.0								89.4
61	13+00	26.8	FT	LT	TO	62	13+00	17.0	FT	LT											9.8				0.3
62	13+00	17.0	FT	LT	TO	63	13+20	17.0	FT	RT			39.4												11.8
63	13+20	17.0	FT	RT	TO	65	13+50	24.5	FT	RT			30.9												11.4
64	13+84	48.0	FT	RT	TO	65	13+50	24.5	FT	RT			31.0								10.0				4.7
65	13+50	24.5	FT	RT	TO	70	11+59	24.5	FT	RT							181.0						10.0		80.1
70	11+59	24.5	FT	RT	TO	75	10+83	24.5	FT	RT		76.3													27.0
71	12+00	26.8	FT	LT	TO	70	11+59	24.5	FT	RT			39.5								26.0				11.1
72	10+49	23.6	FT	LT	TO	73	10+92	21.6	FT	LT											43.0				9.3
73	10+92	21.6	FT	LT	TO	74	10+83	17.0	FT	RT			35.0								5.0				9.4
74	10+83	17.0	FT	RT	TO	75	10+83	24.5	FT	RT			7.5												0.6
75	10+83	24.5	FT	RT	TO	85	9+25	24.5	FT	RT								158.0							24.5
83	9+25	17.0	FT	LT	TO	84	9+25	17.0	FT	RT			34.0												7.3
84	9+25	17.0	FT	RT	TO	85	9+25	24.5	FT	RT			7.5												0.7
85	9+25	24.5	FT	RT	TO	95	7+54	9.5	FT	RT							157.0							15.0	148.8
89	7+90	26.8	FT	RT	TO	95	7+54	9.5	FT	RT			25.0								15.0				6.0
88	7+90	26.8	FT	LT	TO	95	7+54	9.5	FT	RT			30.0								21.0				9.5
90	7+53	37.0	FT	LT	TO	95	7+54	9.5	FT	RT												46.5			42.8
95	7+54	9.5	FT	RT	TO	100	3+54	9.5	FT	RT								379.0						21.0	445.5
99	3+75	19.0	FT	LT	TO	100	3+54	9.5	FT	RT				35.3											5.0
100	3+54	9.5	FT	RT	TO	105	0+84	9.5	FT	RT		255.0												15.0	194.0
105	0+84	9.5	FT	RT	TO							42.6													
										TOTAL	102.0	373.9	1112.2	479.3	156.1	480.0	413.0	537.0	335.0	475.0	205.8	46.5	10.0	51.0	3015

ROBINSON ENGINEERING, LTD.
CONSULTING REGISTERED PROFESSIONAL ENGINEERS AND PROFESSIONAL LAND SURVEYORS
17000 SOUTH PARK AVENUE SOUTH HOLLAND, ILLINOIS 60473
(708) 331-6700 FAX (708) 331-3626

© COPYRIGHT 2004

ILLINOIS DESIGN FIRM REGISTRATION NO. 184001128.

OAK PARK AVENUE RECONSTRUCTION
115TH STREET TO 111TH STREET
PIPE SCHEDULE

WORTH, ILLINOIS

REVISIONS		
No.	Date	Remarks

Drawn by:	EC	Date:	3/31/04
Checked by:	JMN	Scale:	NA
Sheet	of	Project No.	02-162

02162-PIPE-01