

* 03-00182-00-RS
CONTRACT NO. 87275

SUMMARY OF QUANTITIES

ITEM NUMBER	ITEM	UNIT	CONST. TYPE CODE I-000 QUANTITY
* 20200100	EARTH EXCAVATION	CU YD	3088
* 20201500	SUB-BASE GRANULAR MATERIAL, TYPE B	TON	2530
* 20400800	FURNISHED EXCAVATION	CU YD	127
* 20800150	TRENCH BACKFILL	CU YD	22
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	450
* 21101505	TOPSOIL EXCAVATION AND PLACEMENT	CU YD	1138
* 21301052	EXPLORATION TRENCH 52" DEPTH	FOOT	500
# 25000100	SEEDING, CLASS 1	ACRE	2.15
# 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	195
# 25000500	PHOSPHOROUS FERTILIZER NUTRIENT	POUND	195
# 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	195
*# 25100115	MULCH, METHOD 2	ACRE	4.3
# 25100630	EROSION CONTROL BLANKET	SQ YD	530
28000255	TEMPORARY EROSION CONTROL SEEDING	ACRE	2.15
* 28000300	TEMPORARY DITCH CHECKS	EACH	14
* 28000400	PERIMETER EROSION BARRIER	FOOT	1425
28000500	INLET AND PIPE PROTECTION	EACH	13
28500100	FABRIC FORMED CONCRETE REVETMENT MATS	SQ YD	360
35102000	AGGREGATE BASE COURSE, TYPE B 8"	SQ YD	319
35300400	PORTLAND CEMENT CONCRETE BASE COURSE 9"	SQ YD	360
40600300	AGGREGATE (PRIME COAT)	TON	320
* 40600980	BITUMINOUS SURFACE REMOVAL--BUTT JOINT	SQ YD	1838
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL--BUTT JOINT	SQ YD	187
40600990	TEMPORARY RAMP	SQ YD	388
40800040	INCIDENTAL BITUMINOUS SURFACING	TON	1200
44000030	BITUMINOUS SURFACE REMOVAL (VARIABLE DEPTH)	SQ YD	2160
* 44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	971
44003100	MEDIAN REMOVAL	SQ FT	255
44004000	PAVED DITCH REMOVAL	FOOT	296
44201341	CLASS C PATCHES, TYPE II, 9 INCH	SQ YD	13
44201345	CLASS C PATCHES, TYPE III, 9 INCH	SQ YD	45
*# 44300300	AREA REFLECTIVE CRACK CONTROL TREATMENT, SYSTEM A	SQ YD	65331
48101200	AGGREGATE SHOULDERS, TYPE B	TON	7050
48202000	BITUMINOUS SHOULDERS SUPERPAVE	TON	50
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	1
* 550A0120	STORM SEWERS, CLASS A, TYPE 1 24"	FOOT	34
* 55101200	STORM SEWER REMOVAL 24"	FOOT	40
60500090	REMOVING INLETS TO MAINTAIN FLOW	EACH	2
* 60600095	CLASS SI CONCRETE (OUTLET)	CU YD	4
* 60604400	COMBINATION CONCRETE CURB & GUTTER, TYPE B-6.18	FOOT	891
60616110	PAVED DITCH, TYPE A-30	FOOT	297
67100100	MOBILIZATION	L SUM	1
* 70103700	TRAFFIC CONTROL COMPLETE	L SUM	1
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	4750
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	550
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1900
72000100	SIGN PANEL - TYPE 1	SQ FT	40
72000200	SIGN PANEL - TYPE 2	SQ FT	37.5
# 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	217.2
# 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	9665
# 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1060
# 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	1450
# 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	100
# 78000610	THERMOPLASTIC PAVEMENT MARKING - LINE 16"	FOOT	45
# 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	200
# 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	312
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	32
*# 81012400	CONDUIT IN TRENCH, 1 1/4" DIA., PVC	FOOT	1135
*# 81012700	CONDUIT IN TRENCH, 2 1/2" DIA., PVC	FOOT	140
*# 81400115	HANDHOLE TO BE ADJUSTED	EACH	5
# 81400400	CONCRETE HANDHOLE	EACH	4
*# 81500200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	1275
# 87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	1500
# 87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	4715
*# 87700200	STEEL MAST ARM ASSEMBLY AND POLE, 32 FT.	EACH	1
*# 87700240	STEEL MAST ARM ASSEMBLY AND POLE, 40 FT.	EACH	1
*# 87700250	STEEL MAST ARM ASSEMBLY AND POLE, 42 FT.	EACH	1
87800100	CONCRETE FOUNDATION, TYPE A	FOOT	6
87800415	CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER	FOOT	3
# 88200410	TRAFFIC SIGNAL BACKPLATE, LOUVERED, FORMED PLASTIC	EACH	14
*# 88500100	INDUCTIVE LOOP DETECTOR	EACH	19
# 88600100	DETECTOR LOOP, TYPE I	FOOT	1800
*# 89502200	MODIFY EXISTING CONTROLLER	EACH	1
* 89502385	REMOVE EXISTING CONCRETE FOUNDATION	EACH	5
X0300624	RAILROAD PROTECTIVE LIABILITY INSURANCE, (SPECIAL)	EACH	1
* X0322533	REMOVE EXISTING MAST ARM ASSEMBLY AND POLE	EACH	3
X3550500	BITUMINOUS BASE COURSE, SUPERPAVE 8"	SQ YD	1842
* X4066424	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N50	TON	6165
X4066614	BITUMINOUS CONCRETE BINDER COURSE, SUPERPAVE, 1L-19.0, N50	TON	7115
X4066765	LEVELING BINDER (MACHINE METHOD), SUPERPAVE N50	TON	2505
X4400100	PORTLAND CEMENT CONCRETE SURFACE REMOVAL (VARIABLE DEPTH)	SQ YD	545

ITEM NUMBER	ITEM	UNIT	CONST. TYPE CODE I-000 QUANTITY
# X8801300	SIGNAL HEAD ,POLYCARBONATE, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	2
# X8801310	SIGNAL HEAD ,POLYCARBONATE, LED, 1-FACE, 3-SECTION, MAST ARM MOUNTED	EACH	4
# X8801650	SIGNAL HEAD ,POLYCARBONATE, LED, 1-FACE, 4-SECTION, with one DUAL-Indication Section, bracket mounted	EACH	4
# X8801600	SIGNAL HEAD ,POLYCARBONATE, LED, 1-FACE, 4-SECTION with one DUAL-INDICATION SECTION, Bracket mounted	EACH	4
* X8950300	REMOVE EXISTING SIGNAL HEAD AND POST	EACH	2
* X8950305	REMOVE EXISTING SIGNAL HEAD	EACH	12
* XX000802	COMBINATION CONCRETE CURB AND GUTTER OUTLET, SPECIAL	EACH	3
* 40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	9325
* XX006473	STORM SEWER, DUCTILE IRON PIPE, CLASS 50 24"	FOOT	20
*# XX006474	ELECTRICAL CABLE IN CONDUIT, SIGNAL, NO. 14 5C (SPECIAL)	FOOT	1435
X006475	MANHOLE TY. A, 4' DIA., W/SALV. TY. 50 F&G, CVER EXISTING STORM SEWER	EACH	2
* SEE SPECIAL PROVISIONS			
# SPECIALTY ITEM			