

ROUTE NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
C.H. 5	85-00043-00-RS	DEWITT	79	4
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

CONTRACT No. 91316

**ROADWAY SCHEDULE**

LOCATION	AGGREGATE BASE COURSE TYPE B 12"	BITUMINOUS MATERIALS (PRIME COAT)	AGGREGATE PRIME COAT	BITUMINOUS SURFACE REMOVAL BUTT-JOINT	TEMPORARY RAMP	AGGREGATE SHOULDER TYPE B	LEVELING BINDER MACHINE METHOD SUPERPAVE	BIT. SURF. COURSE SUPERPAVE 1 1/2" MIX C N50	AGG. SURF. COURSE TYPE B	INCIDENTAL BITUMINOUS SURFACING 3"	CONCRETE MEDIAN SURFACE 4"
	TON	GAL	TON	SQ YD	SQ YD	TON	TON	TON	TON	TON	SQ YD
MAINLINE											
STA. 10+09.52 TO STA. 276+18.239	2,576	7,402	126	208	22	2,626	8,936	5,509			141
ENTRANCES & MAILBOX TURNOUTS		166				27			246	269	
SIDE ROADS		93	2	405	132	35	78	78			
TOTAL	2,576	7,661	128	613	154	2,688	9,014	5,587	246	269	141

**SEEDING**

PROJECT	SEEDING CLASS 2 SPECIAL	TEMPORARY EROSION CONTROL SEEDING	NITROGEN FERTILIZER NUTRIENT	PHOSPHORUS FERTILIZER NUTRIENT	POTASSIUM FERTILIZER NUTRIENT	MULCH METHOD 2
	ACRE	LBS	LBS	LBS	LBS	TON
PROJECT	19	7,600	1,710	1,710	1,710	38
TOTAL	19	7,600	1,710*	1,710*	1,710*	38*

\* INCLUDED IN PAY ITEM SEEDING CLASS 2 SPECIAL

**PAVEMENT MARKING**

LOCATION	PERMANENT PAVEMENT MARKING						TEMPORARY						WORK ZONE PAVEMENT MARKING REMOVAL	SHORT TERM 4" YELLOW CENTERLINE	
	PAINT			THERMOPLASTIC			PAINT			THERMOPLASTIC					
	4" WHITE EDGE LINE	4" SINGLE YELLOW NO PASSING	4" YELLOW SKIP DASHED CENTERLINE	6" WHITE EDGE LINE	12" WHITE DIAGONAL	24" WHITE STOP LINE	4" WHITE EDGE LINE	4" SINGLE YELLOW NO PASSING	4" YELLOW SKIP DASHED CENTERLINE	6" WHITE EDGE LINE	12" WHITE DIAGONAL	24" WHITE STOP LINE			
FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	
MAIN LINE (2 LIFTS)															
CL STA. 10+09 TO CL STA. 276+18															
LT & RT STA. 10+39 TO LT & RT STA. 276+18	52,781		13,252	6,652			52,781	13,252	6,652					1,756	5,322
RT 169+23															14
LT 169+71															14
RT 276+04															11
ISLAND					160	103				160	103	18			
CL STA. 10+09 TO CL STA. 55+00															
RT CL 26+00 TO RT CL 40+00		1,400		1,123					1,400			1,123			
LT CL 45+00 TO LT CL 58+00		1,300						1,300							
RT CL 55+00 TO RT CL 73+00		1,800						1,800							
CL STA. 58+00 TO CL STA. 80+00			55							55					
LT CL 75+00 TO LT CL 92+00		1,700						1,700							
RT CL 80+00 TO RT CL 92+00		1,200						1,200							
CL STA. 92+00 TO CL STA. 133+00				1,025						1,025					
LT CL 99+00 TO LT CL 108+50		950						950							
RT CL 112+00 TO RT CL 122+00		1,000						1,000							
RT CL 129+00 TO RT CL 139+00		1,000						1,000							
LT CL 133+00 TO LT CL 158+00		2,500						2,500							
CL STA. 139+00 TO CL STA. 276+00				3,425						3,425					
RT CL 179+00 TO RT CL 191+50		1,250						1,250							
LT CL 199+00 TO LT CL 211+50		1,250						1,250							
RT CL 246+00 TO RT CL 257+00		1,100						1,100							
LT CL 273+00 TO LT CL 276+00		300						300							
SIDEROADS															
LAKE FORK RD	94	60					94	60							
SHILOH RD	94	60				36	94	60			36				
JEFFERSON	94	60				36	94	60			36				
OSPUR (CH 15)	94	60					94	60							
AIRPORT RD	94	60				36	94	60			36				
SUBTOTAL	53,251	30,302	12,280	160	103	165	53,251	30,302	12,280	160	103	165	1,756	5,322	
TOTAL		95,833		160	103	165		95,833		160	103	165	1,756	5,322	

NOTE:

EXISTING NO PASSING ZONES TO BE RETAINED EXCEPT IN AREAS OF RE-CONSTRUCTION. CONTRACTOR TO VERIFY LOCATION OF EXISTING NO PASSING ZONES.

COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	
LOCATION	FOOT
RT. STA. 275+96.20 TO STA. 276+11.34 (ISLAND)	34
TOTAL	34

COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.06	
LOCATION	FOOT
RT. STA. 275+96.20 TO STA. 276+11.34 (ISLAND)	18
TOTAL	18

CONCRETE MEDIAN SURFACE, 4"	
LOCATION	SQ FT
RT. STA. 275+96.20 TO STA. 276+11.34 (ISLAND)	141
TOTAL	141

SIGNING			
LOCATION	SIGN PANEL TYPE 1		METAL POST TYPE A
	TYPE	SQ FT	FOOT
C.H. 5			
54' RT. STA. 275+81.21	R1-1	6.3	14
19' RT. STA. 276+08.99	R1-1	6.3	14
TOTAL		12.6	28

**HLR**  
 Roe, Berry and Associates  
 A Division of Hampton, Lenzini and Renwick, Inc.  
 CIVIL & STRUCTURAL ENGINEERS  
 3085 Stevenson Drive  
 Suite 201  
 Springfield, Illinois 62703  
 217-546-3400  
 P.O. Box 1036  
 DuQuoin, Illinois 62832  
 618-790-4637

Account Number 03-29-0007-1  
 Date: 10-17-05  
 DESIGNED: L.F.S. CHECKED: DRAWN: TWK

**SCHEDULE OF QUANTITIES**  
 SECTION 85-00043-00-RS  
 C.H. 5  
 DEWITT COUNTY

REV. DATE: 12-22-05