

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
777	10(B-1, BR-2)	MONTGOMERY	104	12
STA.		TO STA.		
FED. ROAD DIST. NO. 8		ILLINOIS FED. AID PROJECT		

EARTHWORK SCHEDULE, IL RTE. 185

LOCATION	STAGE 0			STAGE 1			STAGE 2			STAGE 3			STAGE 4			TOTALS		
	EXC (CU YD)	EMB (CU YD)	BALANCE * (CU YD)	EXC (CU YD)	EMB (CU YD)	BALANCE * (CU YD)	EXC (CU YD)	EMB (CU YD)	BALANCE * (CU YD)	EXC (CU YD)	EMB (CU YD)	BALANCE * (CU YD)	EXC (CU YD)	EMB (CU YD)	BALANCE * (CU YD)	EXCAVATION (CU YD)	EMBANKMENT (CU YD)	BALANCE (CU YD)
MAINLINE (IL 185)																		
489+00.00				0.0	0.0	0.0	0.0	0.0	0.0	15.0	0.0	15.0	15.4	4.4	9.8	30.4	4.4	24.8
490+00.00				0.0	0.0	0.0	0.0	0.0	0.0	13.3	0.0	13.3	13.9	6.1	6.3	27.2	6.1	19.6
491+00.00				0.0	0.0	0.0	0.0	0.0	0.0	13.7	0.0	13.7	12.0	6.9	3.5	25.7	6.9	17.2
492+00.00				0.0	0.0	0.0	0.0	0.0	0.0	5.9	0.0	5.9	6.3	2.6	3.1	12.2	2.6	9.0
492+50.00																		
OMMISSION FOR BAYOU CREEK				0.0	0.0	0.0	0.0	0.0	0.0									
493+00.00				0.0	0.0	0.0	0.0	0.0	0.0	6.4	28.2	-23.4	5.0	34.9	-31.2	11.4	63.1	-54.6
493+50.00				0.0	0.0	0.0	0.0	0.0	0.0	6.1	28.5	-23.9	2.8	34.9	-32.8	8.9	63.4	-56.8
494+00.00				0.0	0.0	0.0	0.0	0.0	0.0	0.7	0.1	0.6	0.0	0.0	0.0	0.7	0.1	0.6
494+06.30	0.0	13.7	-13.7	5.9	31.8	-27.3	0.0	0.0	0.0	5.6	0.7	4.7	0.0	0.0	0.0	11.5	46.2	-37.6
495+00.00	17.6	65.4	-52.2	11.5	81.7	-73.1	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	29.1	147.0	-125.2
496+00.00	18.7	75.9	-61.9	6.1	67.2	-62.6	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	24.8	143.1	-124.5
497+00.00	20.7	73.3	-57.8	1.9	134.1	-132.7	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	207.4	-207.4
499+00.00	0.0	7.5	-7.5	0.0	31.2	-31.2	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	38.7	-38.7
499+65.49																		
OMMISSION FOR SHOAL CREEK																		
502+00.00	26.5	207.0	-187.2	0.0	35.9	-35.9	207.4	183.1	-27.5	0.0	0.0	0.0	0.0	0.0	0.0	233.9	426.0	-250.6
503+00.00	149.6	250.9	-138.7	1.9	20.2	-18.8	254.6	198.7	-7.7	0.0	0.0	0.0	0.0	0.0	0.0	406.1	469.8	-165.2
504+00.00	203.0	62.2	125.2	1.9	1.9	-0.5	73.5	133.0	-77.8	0.0	0.0	0.0	0.0	0.0	0.0	278.3	197.0	32.0
505+00.00	108.9	42.0	56.3	0.0	0.0	0.0	48.9	62.4	-25.7	0.0	0.0	0.0	0.0	0.0	0.0	157.8	104.4	27.2
506+00.00	66.7	26.5	33.6	0.0	0.0	0.0	22.6	30.0	-13.1	0.0	0.0	0.0	0.0	0.0	0.0	89.3	56.5	18.7
507+00.00																		
IL 185 TOTALS (CUBIC YARDS)	612	827	-884	29	404	-382	607	607	-152	67	58	6	55	90	-41	1347.3	1982.9	-911.5

* A 25% SHRINKAGE FACTOR IS REFLECTED IN THE BALANCE FOR THE VOLUME OF EXCAVATION AND EMBANKMENT.

SCHEDULE CONTINUES ON NEXT SHEET

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULE OF QUANTITIES
 FAP 777 (IL RTE. 185)
 SECTION 10(B-1, BR-2)
 MONTGOMERY COUNTY

SCALE: VERT. _____
 HORIZ. _____
 DATE _____ DRAWN BY _____
 CHECKED BY _____