CONTRACT NO. 92667

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
111	10(B-1,BR-2)	MONTGOMERY	104	13
STA. _____		TO STA._____		
FED. ROAD DIST. NO. 8	ILLINOIS	FED. AID PROJECT		

EARTHWORK SCHEDULE, TOWNSHIP ROAD 318

LOCATION	TOTALS EXC (CU YD)	EMB (CU YD)	BALANCE * (CU YD)
TR318			
10+25.00			
	24.3	28.1	-9.9
10+50.00			
	13.7	76.8	-66.5
10+75.00			
	7.4	102.5	-96.9
11+00.00			
	3.1	113.1	-110.8
11+25.00			
	3.9	119.3	-116.4
11+50.00			
	16.2	100.8	-88.6
11+75.00			
	16.9	77.4	-64.7
12+00.00			
	5.3	54.0	-50.0
12+25.00			
	6.7	25.1	-20.1
12+50.00			
	7.9	8.1	-2.2
12+75.00			
	10.0	1.9	7.6
13+00.00			
	16.7	0.3	16.4
13+25.00			
	22.1	0.0	22.1
13+50.00			
T.R. 318 TOTALS (CUBIC YARDS)	154	707	-580

GRAND TOTALS FOR PROJECT

PROJECT TOTALS		
EXCAVATION (CU YD)	EMBANKMENT (CU YD)	BALANCE * (CU YD)
1502	2690	-1492

* A 25% SHRINKAGE FACTOR IS REFLECTED IN THE BALANCE FOR THE VOLUME OF EXCAVATION AND EMBANKEMENT.

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

FAP 777 (IL RTE. 185)
SECTION 10(B-1, BR-2)
MONTGOMERY COUNTY

SCALE: VERT. HORIZ.
DATE
DRAWN BY
CHECKED BY

PLOT DATE = 1/23/2006
FILE NAME = d:\projects\ed536594\shtsnoq.dgn
PLOT SCALE = 50.0000 ' / IN.
USER NAME = alaglert