

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
777	10(B-1, BR-2)	MONTGOMERY	104	19
STA.		TO STA.		
FED. ROAD DIST. NO. 2		ILLINOIS FED. AID PROJECT		

BITUMINOUS CONCRETE SURFACE COURSE,
SUPERPAVE, MIX C, N50

STA	TO	STA	LENGTH (FT)	WIDTH (FT)	T (")	AREA (SQ YD)
TR 318						
10+12.00		10+43.22	31.22	VARIES	1.5	112.0
IL 185						
491+00.00		492+00.00	100.00	25.62	1.5	199.3
492+00.00		492+48.00	48.00	25.42	1.5	135.6
492+94.00		493+50.00	56.00	25.81	1.5	160.6
493+50.00		494+00.00	50.00	25.98	1.5	144.3
494+00.00		494+06.30	6.30	25.90	1.5	18.1
494+06.30		495+00.00	93.70	26.30	1.5	273.8
495+00.00		496+00.00	100.00	26.66	1.5	296.2
496+00.00		497+00.00	100.00	26.55	1.5	295.0
497+00.00		498+00.00	100.00	26.33	1.5	292.6
498+00.00		499+00.00	48.00	26.49	1.5	294.3
499+00.00		499+79.14	79.14	26.85	1.5	236.1
501+52.54		502+00.00	47.46	24.25	1.5	127.7
502+00.00		503+00.00	100.00	24.56	1.5	272.8
503+00.00		504+00.00	100.00	25.91	1.5	287.9
504+00.00		505+00.00	100.00	26.07	1.5	289.7
505+00.00		505+50.00	50.00	26.05	1.5	144.7
IL 185 BITUMINOUS SHOULDERS						
488+53.00		492+48.15	LT 395.15	4	1.5	175.6
492+93.88		493+80.00	LT 86.12	4	1.5	38.3
494+50.00		499+37.00	LT 487.00	6	1.5	324.7
501+24.68		501+54.68	LT 30.00	6 AVG	1.5	20.0
501+54.68		504+40.00	LT 285.32	8	1.5	253.6
504+40.00		505+00.00	LT 60.00	6 AVG	1.5	40.0
505+00.00		509+35.00	LT 435.00	4	1.5	193.3
509+35.00		509+71.00	LT 36.00	2.5 AVG	1.5	10.0
488+74.00		492+48.15	RT 374.15	4	1.5	166.3
492+93.88		499+35.00	RT 641.12	6	1.5	427.4
501+09.60		508+70.00	RT 760.40	8	1.5	675.9

TOTAL = 5905.8 SQ YD
496.1 TONS

BITUMINOUS CONCRETE SURFACE
COURSE BREAKDOWN BY LOCATIONS

LOCATION	TOTAL AREA (SQ YD)	TOTAL TONS
TR 318	112.0	9.4
IL 185	3468.7	291.4
IL 185 BIT. SHLDRS.	2325.1	195.3

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULE OF QUANTITIES
FAP 777 (IL RTE. 185)
SECTION 10(B-1, BR-2)
MONTGOMERY COUNTY
SCALE: VERT. _____ HORIZ. _____
DATE _____ DRAWN BY _____ CHECKED BY _____

PLOT DATE = 1/23/2006
PLOT SCALE = 500000
USER NAME = alejandr