

F.A.S.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
813	02-00857-00-RS	EDWARDS	4	4
FED ROAD DIST. NO. 7		ILLINOIS	BONEGAP ROAD (NORTH)	

LEC JOB # H041018ED
 CONTRACT NO. 95447

SCHEDULE OF PAVEMENT MARKINGS

STATION	TO	STATION	LOCATION	LENGTH - FOOT
0+00		160+00	CENTERLINE	4000
			EDGELINE	
0+00		26+47	RT.	2647
26+87		53+15	RT.	2628
53+55		79+83	RT.	2628
80+10		106+55	RT.	2645
106+90		160+00	RT.	5310
			EDGELINE	
0+00		53+20	LT.	5320
53+51		79+85	LT.	2634
80+12		106+63	LT.	2651
106+90		160+00	LT.	5310
			NO PASSING	
30+98		36+44	RT.	546
37+94		43+24	LT.	530
57+99		62+02	RT.	403
64+90		69+20	LT.	430
				TOTAL 37,682

THE ABOVE QUANTITY IS SHOW IN THE PAVEMENT MARKING-LINE 4" IN THE SUMMARY OF QUANTITIES.

SCHEDULE OF MAILBOX TURNOUTS

STATION	LOCATION	EST. QUANTITY ALLOWED TONS
26+80	LT.	2.5
37+60	LT.	1.7
122+80	LT.	2.8
159+53	LT.	3.8
		10.8

THE ABOVE QUANTITY IS INCLUDED IN THE BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "C", N50 IN THE SUMMARY OF QUANTITIES.

SCHEDULE OF PRIVATE AND FIELD ENTRANCES

STATION	LOCATION	BC, SC SUPER "C" N50 (IN TONS)
13+17	RT.	2.4
13+17	LT.	2.9
18+66	LT.	2.6
18+71	RT.	2.2
19+95	LT.	3.5
23+26	LT.	2.8
26+59	LT.	1.8
33+40	LT.	2.5
37+20	LT.	2.1
37+77	LT.	1.5
42+25	RT.	1.7
45+50	RT.	2.1
45+56	LT.	2.0
50+72	LT.	1.8
50+74	RT.	1.8
60+16	LT.	2.0
67+04	RT.	2.3
67+09	LT.	1.1
67+55	LT.	2.1
73+50	LT.	2.4
93+55	RT.	3.3
122+53	LT.	2.3
123+29	LT.	1.5
126+84	RT.	2.1
127+53	LT.	2.7
133+20	LT.	3.9
136+84	RT.	2.4
146+31	RT.	1.9
146+47	LT.	2.1
150+33	LT.	2.0
151+73	RT.	2.5
159+62	RT.	1.9
159+72	LT.	1.6
TOTAL		73.8

THE ABOVE QUANTITY IS INCLUDED IN THE BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "C", N50 IN THE SUMMARY OF QUANTITIES.



PROFESSIONAL DESIGN FIRM
 LAND SURVEY &
 PROFESSIONAL ENGINEERING CORPORATION

184-00887 (02/27/99)
 (618) 263-3327



MICHAEL L. G. C. L.
 GUSTIN N. BUNTING
 NAME
 Signature
 DATE 10-27-05
 11-30-05 EXPIRES

SCHEDULE OF PAV'T REMOVAL AND REPLACEMENT SPECIAL

STATION	TO	STATION	LOCATION	WIDTH (FEET)	SQ. YD.	TON
0+00		0+50	RT. EDGE	VARIES	32.0	16.1
0+00		0+50	LT. EDGE	VARIES	40.0	20.2
88+36		88+92	RT. EDGE	4.0	24.9	12.5
144+93		146+50	RT. EDGE	3.0	52.3	26.4
				TOTALS	149.2	75.2

THE SCHEDULE ABOVE REFLECTS APPROXIMATE LOCATION AND ESTIMATED QUANTITIES. THE ACTUAL AREAS SHALL BE LOCATED AND MARKED BY THE ENGINEER PRIOR TO CONSTRUCTION. THE ABOVE QUANTITY IS INCLUDED IN PAVEMENT REMOVAL AND REPLACEMENT SPECIAL IN THE SUMMARY OF QUANTITIES.

SCHEDULE OF AGGREGATE SHOULDER STONE IN TANGENT

STATION	TO	STATION	LOCATION	ALLOWED TONS EST. QUANTITY
0+00		160+00	LT.	528.3
0+00		160+00	RT	624.3
TOTAL				1152.6

THE ABOVE QUANTITY IS FOR THE ENTIRE SECTION AND IS INCLUDED IN THE QUANTITY FOR AGGREGATE SHOULDERS, TYPE B IN THE SUMMARY OF QUANTITIES.