

SUMMARY OF QUANTITIES

FBI ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
939701-00022-00-RP	MADISON		72	3
SUMMARY OF QUANTITIES				

CONTRACT NO. 97269

SUMMARY OF QUANTITIES			
CODE NO	ITEM	UNIT	QTY
	<i>5000</i>		
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	103
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	126
20200100	EARTH EXCAVATION	CU YD	6,177
20800150	TRENCH BACKFILL	CU YD	1,321
21400100	GRADING AND SHAPING DITCHES	FOOT	524
25000100	SEEDING, CLASS 1	ACRE	2.2
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	198
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	198
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	198
25100115	MULCH, METHOD 2	ACRE	2.2
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	502
28000400	PERIMETER EROSION BARRIER	FOOT	377
28000500	INLET AND PIPE PROTECTION	EACH	57
28100107	STONE RIPRAP, CLASS A4	SQ YD	17
28200200	FILTER FABRIC	SQ YD	17
30200650	PROCESSING MODIFIED SOILS 12"	SQ YD	10,415
30201500	LIME	TON	201
31100300	SUB-BASE GRANULAR MATERIAL, TYPE A 4"	SQ YD	10,113
35100500	AGGREGATE BASE COURSE, TYPE A 6"	SQ YD	26
35100700	AGGREGATE BASE COURSE, TYPE A 8"	SQ YD	576
40200500	AGGREGATE SURFACE COURSE, TYPE A 6"	SQ YD	200
40800020	BITUMINOUS MATERIALS (PRIME COAT)	TON	1.0
40800030	AGGREGATE (PRIME COAT)	TON	1.5
42000201	PORTLAND CEMENT CONCRETE PAVEMENT 7" (JOINTED)	SQ YD	8,545
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	966
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	233
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	30,314
42400800	DETECTABLE WARNINGS	SQ. FT.	270
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	828
44000400	GUTTER REMOVAL	FOOT	1,001
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	531
44000600	SIDEWALK REMOVAL	SQ FT	11,745
50105220	PIPE CULVERT REMOVAL	FOOT	862
54200637	PIPE CULVERTS, TYPE 1, CORRUGATED STEEL OR ALUMINUM CULVERT PIPE 12"	FOOT	106
54215550	METAL END SECTIONS 15"	EACH	1
54215556	METAL END SECTIONS 21"	EACH	1
550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	2,010
550A0360	STORM SEWERS, CLASS A, TYPE 2 15"	FOOT	712

* SPECIALTY ITEMS

SUMMARY OF QUANTITIES			
CODE NO	ITEM	UNIT	QTY
	<i>5000</i>		
550A0380	STORM SEWERS, CLASS A, TYPE 2 18"	FOOT	527
550A0400	STORM SEWERS, CLASS A, TYPE 2 21"	FOOT	24
550B0340	STORM SEWERS, CLASS B, TYPE 2 12"	FOOT	167
550B0360	STORM SEWERS, CLASS B, TYPE 2 15"	FOOT	10
550B0380	STORM SEWERS, CLASS B, TYPE 2 18"	FOOT	624
550B0400	STORM SEWERS, CLASS B, TYPE 2 21"	FOOT	168
60218500	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 3 FRAME AND GRATE	EACH	1
60219000	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 8 GRATE	EACH	5
60219540	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 24 FRAME AND GRATE	EACH	5
60224039	MANHOLES, TYPE A, 6'-DIAMETER, TYPE 24 FRAME AND GRATE	EACH	2
60235700	INLETS, TYPE A, TYPE 3 FRAME AND GRATE	EACH	10
60236200	INLETS, TYPE A, TYPE 8 GRATE	EACH	2
60237470	INLETS, TYPE A, TYPE 24 FRAME AND GRATE	EACH	12
60240220	INLETS, TYPE B, TYPE 3 FRAME AND GRATE	EACH	3
60240328	INLETS, TYPE B, TYPE 24 FRAME AND GRATE	EACH	16
60255500	MANHOLES TO BE ADJUSTED	EACH	8
60500060	REMOVING INLETS	EACH	3
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	5,464
67100100	MOBILIZATION	L SUM	1
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1
70103700	TRAFFIC CONTROL COMPLETE	L SUM	1
* 78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	620
* 78008230	POLYUREA PAVEMENT MARKING TYPE I - LINE 6"	FOOT	719
* 78008250	POLYUREA PAVEMENT MARKING TYPE I - LINE 12"	FOOT	144
* X0322923	SEGMENTAL CONCRETE BLOCK WALL	SQ FT	470
X4080030	INCIDENTAL BITUMINOUS SURFACING, SUPERPAVE, N70	TON	100
XX005135	DRAINAGE PIPE CONNECTION 4"	FOOT	243
XX005468	TIMBER WALL REMOVAL	FOOT	56
Z0000990	AGGREGATE FOR TEMPORARY ACCESS	TON	100
Z0012450	CONCRETE STEPS	CU YD	2.0
Z0041500	PLUG EXISTING CULVERTS	EACH	2
XX006471	STORM SEWERS, TYPE 1, WATERMAIN QUALITY PIPE, SDR-21 12"	FOOT	28
XX006472	STORM SEWERS, TYPE 1, WATERMAIN QUALITY PIPE, SDR-21 18"	FOOT	92
60220914	MANHOLES, TYPE A, SPECIAL, 4'-DIAMETER, TYPE 24 FRAME AND GRATE	EACH	1