

SECTION	COUNTY	SHEET NO.	SHEET NO.
9397 01-00022-00-RP	MADISON	72	8
STA.		TO STA.	

CONTRACT NO. 97269

POLYUREA PAVEMENT MARKINGS				
STATION	LOCATION	12" SOLID WHITE LINE	6" SOLID WHITE LINE	4" SKIP-DASH YELLOW LINE
		FEET	FEET	FEET
LOWER MARINE ROAD				
10+25	CROSS WALK		39.00	
10+33	CROSS WALK		35.00	
10+37	TO 12+88			60.00
10+37	LT STOP BAR	15.00		
12+88	RT STOP BAR	13.00		
12+92	CROSS WALK		30.00	
13+00	CROSS WALK		31.00	
13+58	CROSS WALK		31.00	
13+66	CROSS WALK		30.00	
13+70	RT STOP BAR	15.00		
13+70	TO 30+98			430.00
30+98	RT STOP BAR	15.00		
31+02	CROSS WALK		34.00	
31+08	CROSS WALK		36.00	
31+52	CROSS WALK		36.00	
31+58	CROSS WALK		34.00	
31+63	LT STOP BAR	16.00		
31+63	TO 36+75.01			130.00
CLAY STREET				
10+18	CROSS WALK		57.00	
10+26	CROSS WALK		53.00	
10+30	LT STOP BAR	26.00		
JAMES DRIVE				
10+20	CROSS WALK		64.00	
10+30	CROSS WALK		42.00	
10+34	LT STOP BAR	15.00		
BASS DRIVE				
10+17	CROSS WALK		48.00	
10+23	CROSS WALK		42.00	
10+27	LT STOP BAR	16.00		
KENNETH DRIVE				
9+66	LT STOP BAR	13.00		
9+70	CROSS WALK		33.00	
9+80	CROSS WALK		44.00	
TOTAL		144	719	620.0

EARTHWORK SCHEDULE						
STATION	TO	STATION	EARTH EXCAVATION	EARTH EXCAVATION ADJUSTED FOR SHRINKAGE	EMBANKMENT	EARTHWORK BALANCE WASTE (+) SHORTAGE (-)
			CU YD	CU YD	CU YD	CU YD
10+00.00	TO	36+25.00	6,177.00	4,633.00	1,206.00	3,427.00
TOTAL			6,177.00	4,633.00	1,206.00	3,427.00

TREE REMOVAL				
LOCATION	OFFSET (FEET)		TREE REM. 6 TO 15	TREE REM. OVER 15
			UNIT	UNIT
10+39	32.00	RT		36.00
10+83	32.00	RT		24.00
11+70	36.00	RT	15.00	
18+75	12.00	RT		30.00
28+82	27.22	LT	10.00	
29+04	26.14	LT	12.00	
29+25	25.45	LT	12.00	
29+45	24.25	LT	12.00	
29+66	23.00	LT		18.00
30+12	17.00	LT		18.00
30+33	22.00	LT	12.00	
30+54	23.00	LT	12.00	
30+73	22.00	LT	12.00	
33+76	16.00	LT	6.00	
TOTAL			103	126

SEEDING SCHEDULE								
LOCATION		SEEDING CLASS 2 (ACRE)	NITROGEN FERTILIZER NUTRIENT (POUND)	PHOSPHORUS FERTILIZER NUTRIENT (POUND)	POTASSIUM FERTILIZER NUTRIENT (POUND)	MULCH METHOD 2 (ACRE)	TEMP. SEEDING (INCLUDES 2 APPL.) (POUND)	
STATION	TO STATION							
LOWER MARINE ROAD								
10+20.00	TO 36+25.00	2.0	180	180	180	2.0	456	
KENNETH DRIVE								
4+28.00	TO 9+60.00	0.2	18	18	18	0.2	46	
TOTAL		2.2	198	198	198	2.2	502	

REVISIONS		SCHEDULES
NAME	DATE	
		<p>LOWER MARINE ROAD IMPROVEMENTS CITY OF TROY MADISON COUNTY, ILLINOIS</p>

P:\000139A\dwg\000139A\SCHED.dwg 12/9/2005 10:55:08 AM CST