SUMMARY OF QUANTITIES

ITEM NO.	DESCRIPTION	UNIT	AS AWARDED QUANTITIES	AS BUILT QUANTITIES
AR150510	ENGINEER'S FIELD OFFICE	L.S.	1	
AR401610	BITUMINOUS SURFACE COURSE	TON	1,079	
AR401655	BUTT JOINT CONSTRUCTION	S.Y.	495	
AR401900	REMOVE BITUMINOUS PAVEMENT	S.Y.	16.0	
AR402622	POROUS FRICTION COURSE, 0.10'	S.Y.	5,514	
AR501690	PCC SIDEWALK REMOVAL	S.F.	612	
AR510510	TIE DOWN	EACH	24	
AR603510	BITUMINOUS TACK COAT	GAL.	2,833	
AR620520	PAVEMENT MARKING – WATERBORNE	S.F.	1,763	
AR625510	TAR EMULSION SEAL COAT	S.Y.	1,139	
AR901510	SEEDING	ACRE	0.20	
AR905530	TOPSOILING	S.Y.	902	
AR908520	EXCELSIOR BLANKET	S.Y.	834	

INDEX TO SHEETS

SHEET NO.	DESCRIPTION
1	COVER SHEET
2	SUMMARY OF QUANTITIES AND INDEX TO SHEETS
3	PROPOSED SAFETY PLAN
4	PROPOSED CONSTRUCTION PLAN
5	PROPOSED PAVEMENT PREPARATION PLAN
6	PROPOSED APRON STAKING PLAN
7	PROPOSED TAXIWAY STAKING PLAN
8	PROPOSED PLAN AND PROFILE FOR TAXIWAY
9	PROPOSED MARKING PLAN
10	PROPOSED CROSS-SECTIONS FOR TAXIWAY STA. 0+37.5 TO STA. 1+00
11	PROPOSED CROSS-SECTIONS FOR TAXIWAY STA. 1+20 TO STA. 1+80
12	PROPOSED CROSS-SECTIONS FOR TAXIWAY STA. 2+00 TO STA. 2+60
13	PROPOSED CROSS-SECTIONS FOR APRON STA. 421+40 TO STA. 421+60
14	PROPOSED CROSS-SECTIONS FOR APRON STA. 421+80 TO STA. 422+00
15	PROPOSED CROSS-SECTIONS FOR APRON STA. 422+20 TO STA. 422+40
16	PROPOSED CROSS-SECTIONS FOR APRON STA. 422+60 TO STA. 422+80
17	PROPOSED CROSS-SECTIONS FOR APRON STA. 423+00 TO STA. 423+20
18	PROPOSED CROSS-SECTIONS FOR APRON STA. 423+40 TO STA. 423+60
19	PROPOSED CROSS-SECTIONS FOR APRON STA. 423+72.86 TO STA. 423+80
20	PROPOSED CROSS-SECTIONS FOR APRON STA. 424+00 TO STA. 424+20
21	PROPOSED CROSS-SECTIONS FOR APRON STA. 424+40 TO STA. 424+60
22	PROPOSED CROSS-SECTIONS FOR APRON STA. 424+80 TO STA. 425+00
23	PROPOSED CROSS-SECTIONS FOR APRON STA. 425+20 TO STA. 425+40
24	PROPOSED CROSS-SECTIONS FOR APRON STA. 425+60 TO STA. 425+69.50
25	PROPOSED CROSS-SECTIONS FOR APRON STA. 425+80 TO STA. 426+00

DATE	REVISION	BY

METROPOLIS MUNICIPAL AIRPORT
METROPOLIS, ILLINOIS

IL PROJ.: M30-3540 A.I.P. PROJ.: 3-17-0067-B7

HEI Project No. 816-06APND
Filename R-601SUM.DWG
Scale N/A
Date 09/26/05

LAYOUT	JEO	09/26/05
DRAWN	JEO	09/26/05
REVIEWED	CAH	12/12/05

HANSON
Hanson Professional Services Inc.
1525 South Sixth Street
Springfield, Illinois 62703-2886
Offices Nationwide

PROPOSED APRON REHABILITATION

SUMMARY OF QUANTITIES AND INDEX TO SHEETS

JAN 18, 2006 3:31 PM BKB
I:\AIRPORTS\METROPOLIS\816-06APN\AIRPORT\SHEETS\R-601SUM.DWG - Layout1