

SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT		100% STATE 099-3392 0047				
50102400	CONCRETE REMOVAL	CU YD	10.4	10.4				
50157300	PROTECTIVE SHIELD	SO YD	176	176				
50300255	CONCRETE SUPERSTRUCTURE	CU YD	10.4	10.4				
50300300	PROTECTIVE COAT	SO YD	70	70				
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	1450	1450				
50800515	BAR SPLICERS	EACH	14	14				
52000110	PREFORMED JOINT STRIP SEAL	FOOT	162	162				
70600260	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3	EACH	2	2				
64300370	IMPACT ATTENUATORS (FULLY REDIRECTIVE, WIDE), TEST LEVEL 3	EACH	2	2				
67100100	MOBILIZATION	L SUM	1	1				
70107025	CHANGEABLE MESSAGE SIGN	CAL DA	60	60				
70300150	SHORT TERM PAVEMENT MARKING REMOVAL	SO FT	7680	7680				
70307120	TEMPORARY PAVEMENT MARKING - LINE 4" - TYPE IV TAPE	FOOT	23040	23040				
70400100	TEMPORARY CONCRETE BARRIER	FOOT	1125	1125				

SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT		100% STATE 099-3392 0047				
70400125	PINNING TEMPORARY CONCRETE BARRIER	EACH	25	25				
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	1125	1125				
70600327	IMPACT ATTENUATORS, RELOCATE (FULLY REDIRECTIVE, WIDE), TEST LEVEL 3	EACH	2	2				
* 78009004	MODIFIED URETHANE PAVEMENT MARKING - LINE 4"	FOOT	2600	2600				
* 78009012	MODIFIED URETHANE PAVEMENT MARKING - LINE 12"	FOOT	350	350				
* 78100300	REPLACEMENT REFLECTOR	EACH	50	50				
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	50	50				
78300202	PAVEMENT MARKING REMOVAL - WATER BLASTING	SO FT	1350	1350				
X6700407	ENGINEER'S FIELD OFFICE, TYPE A (D1)	CAL MO	6	6				
X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1				
Z0030850	TEMPORARY INFORMATION SIGNING	SO FT	51.4	51.4				
	* SPECIALTY ITEM							

FILE NAME =	USER NAME = Ivan Diaz	DESIGNED -	REVISED -
pw:\N\dot-pw\benrey.com\PW\DOT Documents\1007 - Off10\5\Dist\1\1\Projects\DOT\222\CAD\dot\Design\DOT\222-stf-co	DRAWN -	CHECKED -	REVISED -
	PLOT SCALE = 100,0000' / 1in	DATE -	REVISED -
	PLOT DATE = 12/20/2022		

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES			
SCALE:	SHEET NO.	OF SHEETS	STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
532	FAP 532 22 BRIDGE	WILL	21	3
CONTRACT NO. 62R68				
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				

1 REVISED SHEET 3/01/2023