

- PRECAST CONCRETE PARKING BLOCK
- PROPOSED GUARD POST
- ⊠ SCARIFY EXISTING SURFACE
- //// GUARDRAIL REMOVAL

GUARD POSTS		
STA.	OFFSET	EACH
117+82.79	36.99	1
117+87.88	40.89	1
117+92.53	45.35	1

CONTROL POINT #77
 STA. 118+22.20, 24.09' LT.
 N 1384211.29
 E 2122932.12
 ELEV.= 709.21

SCARIFY EXISTING SURFACE
 STA. 117+55 LT. TO STA. 118+48 LT, 261.2 SQ. YD.
 REMOVE AND REINSTALL PARKING BLOCKS
 STA. 117+85 LT. TO STA. 117+93 LT, 2 EACH
 STEEL PLATE BEAM GUARDRAIL REMOVAL
 STA. 117+82 LT. TO STA. 117+91 LT, 9 FT.
 PAINT PAVEMENT MARKING LINE 6"
 STA. 117+83 LT. TO STA. 117+96 LT, 36'
 STA. 117+62.21, 36.92' LT.

EXIST. CURVE C38
 PI STA. = 118+32.94
 $\Delta = 92^\circ 11' 39''$ (RT)
 $D = 76^\circ 23' 40''$
 $R = 75.00'$
 $T = 77.93'$
 $L = 120.68'$
 $E = 33.16'$
 P.C. STA. = 117+55.01
 P.T. STA. = 118+75.69

EXIST. CURVE C39
 PI STA. = 119+15.56
 $\Delta = 13^\circ 59' 11''$ (RT)
 $D = 17^\circ 37' 46''$
 $R = 325.00'$
 $T = 39.87'$
 $L = 79.34'$
 $E = 2.44'$
 P.C. STA. = 118+75.69
 P.T. STA. = 119+55.03



MATCHLINE 114+25

MATCHLINE 120+75

FILE NAME =	USER NAME = #USER#	DESIGNED - R.H.D.	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	ARGYLE LAKE STATE PARK MAIN ROAD	F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
#FILEL#		DRAWN - J.T.T.	REVISED -			ARGYLE LAKE STATE PARK	MCDONOUGH	162	39	
		CHECKED - T.T.P.	REVISED -			CONTRACT NO. 46158				
		DATE - 12/09/10	REVISED -			SCALE: 1" = 20'		SHEET NO. 39 OF 162 SHEETS STA. 114+25 TO STA. 120+75		
						FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		