



- TEMPORARY EROSION CONTROL SEQUENCE OF CONSTRUCTION**
- ① ESTABLISH TEMPORARY EROSION CONTROL MEASURES AND ERECT SILT FENCE ALONG SITE BOUNDRIES PRIOR TO MASS EARTHWORK.
  - ② INSTALL DITCH CHECK IMMEDIATLY AFTER DITCH GRADING IS COMPLETED.
  - ③ INSTALL PERMANENT SEEDING BEFORE BEGINNING NEXT CONSTRUCTION STAGE.

FILE NAME = D144410-sh-t-ero.dgn	USER NAME = ulrshkd	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>EROSION CONTROL PLAN IL. ROUTE 47 AT IL. ROUTE 176 (EAST LEG)</b>			F.A.P. RTE. 326	SECTION 105 N-4	COUNTY McHENRY	TOTAL SHEETS 60	NO. 16
	PLOT SCALE = 50.0000' / IN.	DRAWN -	REVISED -		SCALE: 1" = 50'	SHEET NO.	OF SHEETS	STA.	TO STA.	CONTRACT NO. 60K18		
	PLOT DATE = 12/20/2010	CHECKED -	REVISED -		ILLINOIS FED. AID PROJECT							
		DATE -	REVISED -									