SIGNING SCHEDULE

				SIGN PANELS														SIGN SUPPORTS					
				EXISTING PANEL DIMENSIONS		PROPOSED PANEL DIMENSIONS		SIGN AREA	SIGN PANEL - TYPE 1	SIGN PANEL - TYPE 2	SIGN PANEL - TYPE 3	REMOVE SIGN PANEL - TYPE 1	REMOVE SIGN PANEL ASSEMBLY - TYPE A	REMOVE SIGN PANEL - TYPE 2	REMOVE SIGN PANEL ASSEMBLY - TYPE B	REMOVE SIGN PANEL - TYPE 3	REMOVE GROUND MOUNTED SIGN SUPPORT	- TELESCOPING STEEL SIGN SUPPORT			WOOD SIGN SUPPORT		
STATION	LT/RT	SIGN NO.	LEGEND/ DESCRIPTION	HEIGHT (L.F.)	WIDTH (L.F.)	HEIGHT (L.F.)	WIDTH (L.F.)	(SQ FT)	(SQ FT)	(SQ FT)	SQ FT)	(EACH)	(EACH)	(EACH)	(EACH)	(SQ FT)	(EACH)	P1 (L.F.)	P2 (L.F.)	PAY LENGTH (L.F.)	P1 (L.F.)	P2 (L.F.)	PAY LENGTH (L.F.)
433+42	RT	NB-53-LP-33	R5-1 (DO NOT ENTER)	3	3	3	3	9	9	-	-	1	-	-	-	-							
434+10	RT	NB-53-WP-34	R5-1 (DO NOT ENTER)	5	4	5	4	20	-	20	-	-	-	-	1	-					17		17
400+68	LT	SB-53-WP-123	R5-I100 (BUCKLE UP)	5	4	1	2	2	2	-	-	-	1	-	-	-					10		10
403+54	LT	SB-53-LP-113	M-3-3 (SOUTH)	1	2	1	2	2	2	-	-	1	-	-	-	-							
403+54	LT	SB-53-LP-114	M1-I100 (ILLINOIS-53)	2	2			0	0	-	-	1	-	-	-	-							
403+54	LT	SB-53-LP-115	M6-1 (LEFT ARROW)	1.25	1.75	2	2	4	4	-	-	1	-	-	-	-							
403+54	LT	SB-53-LP-116	M3-3 (SOUTH)	1	2			0	0	-	-	1	-	-	-	-							
403+54	LT	SB-53-LP-117	M1-I100 (ILLINOIS-53)	2	2			0	0	-	-	1	-	-	-	-							
403+54	LT	SB-53-LP-118	M6-1 (RIGHT ARROW)	1.25	1.75	1.25	1.75	2.1875	2.1875	-	-	1	-	-	-	-							
403+29	LT	SB-53-LP-119	M3-3 (SOUTH)	1	2	1	2	2	2	-	-	1	-	-	-	-							
403+29	LT	SB-53-LP-120	M1-I100 (ILLINOIS-53)	2	2	2	2	4	4	-	-	1	-	-	-	-							
403+29	LT	SB-53-LP-121	M6-3 (UP ARROW)	1.25	1.75	1.25	1.75	2.1875	2.1875	-	-	1	-	-	-	-							
1+20	LT	NB-53-WP-137	W1-8 (CHEVRON)			3	2.5	7.5	7.5	-	-	-	-	-	-	-					15		15
2+40	LT	NB-53-WP-138	W1-8 (CHEVRON)			3	2.5	7.5	7.5	-	-	-	-	-	-	-					15		15
3+60	LT	NB-53-WP-139	W1-8 (CHEVRON)			3	2.5	7.5	7.5	-	-	-	-	-	-	-					15		15
4+80	LT	NB-53-WP-140	W1-8 (CHEVRON)			3	2.5	7.5	7.5	-	-	-	-	-	-	-					15		15
6+00	LT	NB-53-WP-141	W1-8 (CHEVRON)			3	2.5	7.5	7.5	-	-	-	-	-	-	-					15		15
7+20	LT	NB-53-WP-142	W1-8 (CHEVRON)			3	2.5	7.5	7.5	-	-	-	-	-	-	-					15		15
8+40	LT	NB-53-WP-143	W1-8 (CHEVRON)			3	2.5	7.5	7.5	-	-	-	-	-	-	-					15		15
9+60	LT	NB-53-WP-144	W1-8 (CHEVRON)			3	2.5	7.5	7.5	-	-	-	-	-	-	-					15		15
11+92	LT	NB-53-WP-145	W1-8 (CHEVRON)			3	2.5	7.5	7.5	-	-	-	-	-	-	-					15		15
13+02	LT	NB-53-WP-146	W1-8 (CHEVRON)			3	2.5	7.5	7.5	-	-	-	-	-	-	-					15		15
14+22	LT	NB-53-WP-147	W1-8 (CHEVRON)			3	2.5	7.5	7.5	-	-	-	-	-	-	-					15		15
TOTALS									110	20	0	10	1	0	1	0	0	0	0	0	192	0	192
						GRAND TOTALS			447	336	3396	36	12	9	19	3327	5			148			589

200 22ND Street, Suite 216, Lombard, IL 60148
630.705.0110 voice, 630.839.2566 fax
www.mps-il.com
MILLENNIA PROFESSIONAL SERVICES

DESIGNED	- CJD	REVISED	-
DRAWN	- CJD	REVISED	-
CHECKED	- TVN	REVISED	-
DATE	- 1/3/2011	REVISED	-

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

ILLINOIS ROUTE 53
RAND ROAD TO LAKE COOK ROAD

SCALE: SHEET NO. OF SHEETS STA. TO STA.

SIGNING SCHEDULE

Rev.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2592	2010-003 I	COOK	43	6
		CONTRACT NO. 60K21		

FED. ROAD DIST. NO. 1 | ILLINOIS | FED. AID PROJECT

P:\2009\ME090006_VarVar PhII\CADD\W019_IL53\Shts\D160K21-sht-Signschedule.dgn

FILE NAME = P:\2009\ME090006_VarVar PhII\CADD\W019_IL53\Shts\D160K21-sht-Signschedule.dgn
PLOT SCALE = 50.000 ' / IN.
USER NAME = Millennia Professional Services