

CONTRACT 60M63  
TEMPORARY PAVEMENT MARKING AND TEMPORARY ATTENUATOR SCHEDULE

	PAVEMENT MARKING REMOVAL	WET REFLECTIVE TEMPORARY TAPE TYPE III, 4 INCH	WET REFLECTIVE TEMPORARY TAPE TYPE III, 5 INCH	WET REFLECTIVE TEMPORARY TAPE TYPE III, 8 INCH	WET REFLECTIVE TEMPORARY TAPE TYPE III, 12 INCH	WET REFLECTIVE TEMPORARY TAPE, TYPE III, LETTERS AND SYMBOLS	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	IMPACT ATTENUATORS, TEMPORARY (SEVERE USE, NARROW), TEST LEVEL 3	IMPACT ATTENUATORS, RELOCATE TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3
STAGE	(SQFT)	(FOOT)	(FOOT)	(FOOT)	(FOOT)	(SQFT)	(EACH)	(EACH)	(EACH)
1	0	11,363	1403	2,528	565	0	3	0	1
2	0	25,465	0	3,063	414	0	0	1	0
3	0	14,138	1517	2,108	414	0	0	0	3
RESURFACING	39,888	119,140	13,044	6,362	1,142	0	0	0	0
<b>TOTAL</b>	<b>39,888</b>	<b>170,106</b>	<b>15,964</b>	<b>14,061</b>	<b>2,535</b>	<b>0</b>	<b>3</b>	<b>1</b>	<b>4</b>

CONTRACT 60M63  
EASTBOUND PAVEMENT MARKING SCHEDULE

LOCATION					THERMOPLASTIC PAVEMENT MARKINGS - LETTERS AND SYMBOLS	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID LINE 4"	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID LINE 5"	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID LINE 8"	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	POLYUREA PAVEMENT MARKING TYPE I - LINE 5"	POLYUREA PAVEMENT MARKING TYPE I - LINE 8"	POLYUREA PAVEMENT MARKING TYPE I - LINE 12"	RAISED REFLECTIVE PAVEMENT MARKER	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)
ALIGNMENT	DIRECTION	DESCRIPTION	STATION	STATION	(SQFT)	(FOOT)	(FOOT)	(FOOT)	(FOOT)	(FOOT)	(FOOT)	(FOOT)	(FOOT)	(FOOT)	(FOOT)	(FOOT)	(EACH)	(EACH)
I80	EB	SHEET 1	88+59.21	95+00.00	0	640.8	645	144	0	118	179	0	0	0	0	0	20	0
I80	EB	SHEET 2	95+00.00	125+00.00	0	5832	178	227	0	42	757	0	0	0	0	0	76	0
I80	EB	SHEET 3	125+00.00	155+00.00	0	6000	0	85	0	0	751	0	0	0	0	0	74	0
I80	EB	SHEET 4	155+00.00	185+00.00	0	6000	0	92	0	0	750	0	0	0	0	0	76	0
I80	EB	SHEET 5	185+00.00	215+00.00	0	6000	0	99	0	0	743	0	0	0	0	0	76	0
I80	EB	SHEET 6	215+00.00	245+00.00	0	6000	0	92	0	0	743	0	0	0	0	0	74	0
I80	EB	SHEET 7	245+00.00	275+00.00	0	4372	1884	242	0	63	678	0	645	81	0	161	70	8
I80	EB	SHEET 8	275+00.00	305+00.00	0	4578	1914	299	0	0	671	151	297	60	296.25	100	74	6
I80	EB	SHEET 9	305+00.00	335+00.00	0	4829	1756	84	0	0	723	0	338	28	0	51	73	4
I80	EB	SHEET 10	335+00.00	361+00.00	0	4,447	0	83	0	0	556	0	466	94	413	0	56	0
I80	EB	SHEET 11	361+00.00	375+00.00	0	0	0	0	0	0	0	0	2,428	350	1,116	278	0	3
I80	EB	SHEET 12	375+00.00	389+00.00	0	0	0	0	0	0	0	0	2,365	350	1,305	208	0	0
I80	EB	SHEET 13	389+00.00	419+00.00	0	4,311	0	66	0	0	539	0	844	211	1,071	10	54	0
I80	EB	SHEET 14	419+00.00	449+00.00	0	6,000	0	90	0	0	750	0	0	0	0	0	75	0
I80	EB	SHEET 15	449+00.00	479+00.00	0	5,664	0	64	0	0	708	0	336	42	0	0	71	3
I80	EB	SHEET 16	479+00.00	505+00.00	0	4,768	694	73	0	0	650	0	0	0	36	0	73	0
I80	EB	SHEET 17	505+00.00	533+00.00	0	4,225	2005	588	0	0	700	88	0	0	1,442	0	87	0
I80	EB	SHEET 18	533+00.00	544+48.00	0	1,443	959	13	0	0	287	0	0	0	0	0	29	0
<b>TOTAL</b>					<b>0</b>	<b>75,110</b>	<b>10,035</b>	<b>2,341</b>	<b>0</b>	<b>223</b>	<b>10,185</b>	<b>239</b>	<b>7,719</b>	<b>1,216</b>	<b>5,679</b>	<b>808</b>	<b>1,058</b>	<b>24</b>