

URBAN

CODE NO.	ITEM DESCRIPTION	UNIT	100% STATE TOTAL	CONSTRUCTION TYPE CODE		
				0005	0014	0005
				1	2	3
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	545			545
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	610			610
20101300	TREE PRUNING (1 TO 10 INCH DIAMETER)	EACH	58			58
20101350	TREE PRUNING (OVER 10 INCH DIAMETER)	EACH	73			73
20700220	POROUS GRANULAR EMBANKMENT	CU YD	261	261		
21101605	TOPSOIL FURNISH AND PLACE, 2"	SQ YD	4,748			4,748
25000210	SEEDING, CLASS 2A	ACRE	4.5			4.5
X2501800	SEEDING, CLASS 4 (MODIFIED)	ACRE	34			34
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	1,125			1,125
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	1,125			1,125
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	1,125			1,125
25000750	MOWING	ACRE	36			36
25003210	INTERSEEDING, CLASS 2A	ACRE	8			8
25100115	MULCH, METHOD 2	ACRE	3			3
25100630	EROSION CONTROL BLANKET	SQ YD	922			922
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	300			300
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	30,318	30,318		
40600300	AGGREGATE (PRIME COAT)	TON	539	539		
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	39	39		
40600895	CONSTRUCT ^{ING} TEST STRIP	EACH	2	2		
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	276	276		
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	357	357		
40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	5,388	5,388		
40603148	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, STONE MATRIX ASPHALT, N80	TON	12,532	12,532		
40603153	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, STONE MATRIX ASPHALT, N80	TON	13,407	12,696	711	
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	4,013	4,013		
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	8,439	8,439		
44000165	HOT-MIX ASPHALT SURFACE REMOVAL, 4"	SQ YD	150,359	150,359		
44002216	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 4"	SQ YD	1,381	1,381		
44201349	CLASS C PATCHES, TYPE I, 10 INCH	SQ YD	20	20		
44201353	CLASS C PATCHES, TYPE II, 10 INCH	SQ YD	25	25		
44201357	CLASS C PATCHES, TYPE III, 10 INCH	SQ YD	20	20		
44201359	CLASS C PATCHES, TYPE IV, 10 INCH	SQ YD	25	25		
44201761	CLASS D PATCHES, TYPE I, 10 INCH	SQ YD	25	25		
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SQ YD	27	27		
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SQ YD	250	250		
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SQ YD	1,106	1,106		
50102400	CONCRETE REMOVAL	CU YD	7.1		7.1	
50104650	SLOPEWALL REMOVAL	SQ YD	212		212	

URBAN

CODE NO.	ITEM DESCRIPTION	UNIT	100% STATE TOTAL	CONSTRUCTION TYPE CODE		
				0005	0014	0005
				1	2	3
50157300	PROTECTIVE SHEILD	SQ YD	1,581			1,581
50300225	CONCRETE STRUCTURES	CU YD	1			1
50300255	CONCRETE SUPERSTRUCTURES	CU YD	5.7			5.7
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	737			737
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	1,422			1,422
50800515	BAR SPLICERS	EACH	14			14
59000200	EPOXY CRACK INJECTION	FOOT	17			17
51100100	SLOPEWALL 4 INCH	SQ YD	212			212
52100520	ANCHOR BOLTS, 1"	EACH	4			4
58700300	CONCRETE SEALER	SQ FT	23,346			23,346
64200105	SHOULDER RUMBLE STRIPS	FOOT	54,104	54,104		
67100100	MOBILIZATION	L SUM	1	1		
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	15	15		
70300240	TEMPORARY PAVEMENT MARKING- LINE 6"	FOOT	9,613	9,613		
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	350	350		
70400100	TEMPORARY CONCRETE BARRIER	FOOT	7,750	7,750		
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	10,175	10,175		
* 72000100	SIGN PANEL - TYPE 1	SQ FT	104	104		
* 72000200	SIGN PANEL - TYPE 2	SQ FT	792	792		
* 72000300	SIGN PANEL - TYPE 3	SQ FT	3,631	3,631		
* 72400100	REMOVE SIGN PANEL ASSEMBLY- TYPE A	EACH	6	6		
* 72400200	REMOVE SIGN PANEL ASSEMBLY- TYPE B	EACH	23	23		
* 72400310	REMOVE SIGN PANEL- TYPE 1	SQ FT	73	73		
* 72400320	REMOVE SIGN PANEL- TYPE 2	SQ FT	356	356		
* 72400330	REMOVE SIGN PANEL- TYPE 3	SQ FT	3,655	3,655		
* 72600100	MILE POST MARKER ASSEMBLY	EACH	11	11		
* 72900200	METAL POST- TYPE B	FOOT	603	603		
* 73000100	WOOD SIGN SUPPORT	FOOT	746	746		
* 73700100	REMOVE GROUND MOUNTED SIGN SUPPORT	EACH	31	31		
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	182	182		
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	64,777	64,777		
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	8,872	8,872		
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	1,607	1,607		
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	35	35		
* 78004220	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B-INLAID- LINE 5"	FOOT	7,544	7,544		
* 78004240	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B-INLAID- LINE 8"	FOOT	997	997		
* 78005110	EPOXY PAVEMENT MARKING - LINE 4"	FOOT	1000	1000		
* 78008210	POLYUREA PAVEMENT MARKING TYPE I- LINE 4"	FOOT	8,634	8,634		
* 78008220	POLYUREA PAVEMENT MARKING TYPE I- LINE 5"	FOOT	1,060	1,060		
* 78008240	POLYUREA PAVEMENT MARKING TYPE I- LINE 8"	FOOT	1,563	1,563		

Rev. 3-1-11

Rev.

USER NAME = tkoeppen@rdg.lisle
 PLOT CONFIG = PDF(Largo).plt
 PLOT SCALE = 1:50
 PLOT DATE = 1/20/2011
 FILE NAME = ...ads34575\016\664-ht-500.dgn

DESIGNED - TCK
 DRAWN - CPK
 CHECKED - DTH
 DATE - 1/21/2011



STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES
 SCALE: N/A SHEET NO. 1 OF 2 SHEETS STA. TO STA.

F.A.I. SECTION COUNTY TOTAL SHEET NO.
 80 99 (2 & 3) RS-3 WILL 200 3
 CONTRACT NO. 60M64
 FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT