

RESURFACING SCHEDULE

LOCATION					POLYMERIZED HMA SURFACE COURSE, SMA, N80	POLYMERIZED HMA BINDER COURSE, SMA, N80	HMA SURFACE COURSE, MIX "D", N70	HMA BINDER COURSE, IL-19.0, N70	HMA SURFACE REMOVAL, 2"	HMA SURFACE REMOVAL, 4"	SHOULDER RUMBLE STRIP
ALIGNMENT	DIRECTION	DESCRIPTION	STATION	STATION	(TON)	(TON)	(TON)	(TON)	(SQ YD)	(SQ YD)	(FOOT)
I-80	EB	MAINLINE	544+48.53	563+00.00	619.25	619.25	320.88	240.22	1578.20	7244.87	3431.78
I-80	EB	MAINLINE	563+00.00	578+00.00	541.33	541.33	200.45	210.00	664.70	6333.33	3000.00
I-80	EB	MAINLINE	578+00.00	578+67.70	24.43	24.43	9.03	9.48	29.80	285.84	135.40
I-80	EB	MAINLINE	578+67.70	581+07.30	119.96	119.96	34.23	34.17	106.70	1315.16	244.05
I-80	EB	MAINLINE	581+07.30	593+00.00	339.90	339.90	178.69	153.33	775.00	4115.75	1767.37
RAYNR-A	EB	RAMP	2+45.73	3+60.20	24.22	24.22	7.48	12.46	0.00	305.25	0.00
RAYNR-A	EB	RAMP	3+60.20	6+11.50	50.04	0.00	43.78	0.00	837.67	0.00	0.00
RAYNR-A	EB	RAMP	7+30.70	10+06.50	54.91	0.00	41.19	0.00	858.04	0.00	0.00
RAYNR-A	EB	RAMP	10+06.50	10+86.60	14.45	0.00	8.82	0.00	225.17	0.00	0.00
RAYNR-A	EB	RAMP	10+86.60	11+41.70	8.91	0.00	4.11	0.00	116.32	0.00	0.00
RAYNR-A	EB	RAMP	11+04.30	11+41.70	6.98	0.00	5.35	0.00	110.12	0.00	0.00
RAYNR-A	EB	RAMP	14+01.20	15+05.45	28.87	0.00	10.38	0.00	350.40	0.00	0.00
I-80	EB	MAINLINE	593+00.00	598+39.40	194.66	194.66	49.07	81.79	0.00	2322.26	899.61
I-80	EB	MAINLINE	596+61.80	598+39.40	61.88	61.88	11.60	19.34	0.00	700.53	0.00
I-80	EB	MAINLINE	598+39.40	599+70.50	90.14	90.14	8.57	14.28	0.00	906.77	262.20
I-80	EB	MAINLINE	599+70.50	601+29.21	104.68	104.68	10.37	17.28	0.00	1058.07	317.42
I-80	EB	MAINLINE	607+00.00	622+00.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
I-80	EB	MAINLINE	622+00.00	625+84.60	0.00	0.00	0.00	0.00	0.00	0.00	0.00
I-80	EB	MAINLINE	625+84.56	635+95.71	645.24	645.24	146.95	144.14	539.84	6790.62	1550.92
CHICAGO-A	EB	RAMP	3+56.67	12+89.32	180.37	180.37	115.12	191.86	0.00	2980.87	0.00
CHICAGO-AA	EB	RAMP	9+92.76	10+56.95	12.77	12.77	7.94	13.23	0.00	208.48	0.00
I-80	EB	MAINLINE	637+73.70	642+20.60	281.38	281.38	53.68	56.69	175.60	2917.29	652.21
CHICAGO-BB	EB	RAMP	2+35.84	8+80.05	127.85	127.85	101.90	169.83	0.00	2354.59	0.00
I-80	EB	MAINLINE	647+00.93	651+29.60	219.68	219.68	33.62	25.95	161.14	2146.78	856.81
I-80	EB	MAINLINE	652+00.00	667+00.00	1116.60	505.60	193.40	242.30	426.00	6244.80	2014.00
I-80	EB	MAINLINE	667+00.00	697+00.00	959.00	959.00	388.80	396.10	1349.00	11392.00	3685.80
I-80	EB	MAINLINE	697+00.00	727+00.00	950.50	950.50	260.00	408.00	135.00	11400.90	5283.90
I-80	EB	MAINLINE	727+00.00	738+00.00	483.30	483.30	138.40	230.70	0.00	5962.80	1747.40
I-80	EB	MAINLINE	738+00.00	753+00.00	542.80	542.80	134.60	224.30	0.00	6448.50	3000.00
I-80	EB	MAINLINE	753+00.00	783+00.00	1239.20	1239.20	307.70	512.90	0.00	14727.30	5160.80
I-80	EB	MAINLINE	783+00.00	813+00.00	1086.00	1086.00	280.10	466.80	0.00	13030.90	6000.00
I-80	EB	MAINLINE	813+00.00	843+00.00	1090.40	1090.40	259.50	432.60	0.00	12825.10	6000.00
I-80	EB	MAINLINE	843+00.00	873+00.00	1116.10	1116.10	253.10	421.80	0.00	12978.30	6052.40
I-80	EB	MAINLINE	873+00.00	885+00.00	520.60	520.60	140.70	234.50	0.00	6323.50	2041.40
I-80	EB	RAMP US30-A	15+00.00	26+61.90	214.80	214.80	150.00	250.10	0.00	3704.20	0.00
I-80	EB	RAMP US30-C	1+48.12	8+00.00	124.40	124.40	83.90	139.80	0.00	2108.90	0.00
I-80	EB	RAMP END	-	-	110.70	110.70	19.80	33.10	0.00	1224.40	0.00

TOTAL	13,306	12,531	4,013	5,387	8,439	150,358	54,103
-------	--------	--------	-------	-------	-------	---------	--------

USER NAME = ckersten(Lisle_R)	DESIGNED - EJB	REVISED - 02/15/11
PLOT CONFIG = PDF03reg_Small.plt	DRAWN - EJB	REVISED -
PLOT SCALE = 1:100	CHECKED - DTH	REVISED -
PLOT DATE = 2/15/2011	DATE - 1/21/2011	REVISED -



STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULES		
SCALE: NTS	SHEET NO. 2 OF 2 SHEETS	STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
80	99 (2 & 3) RS-3	WILL	200	13
CONTRACT NO. 60M64			FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT	