

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE						
				ROADWAY US 45/143RD 80% FED 20% STATE 0003	TRACK RELOCATION 80% FED 20% STATE 0021	LANDSCAPING 80% FED 20% STATE 0003		PLATFORM 80% FED 20% STATE 0003	VILLAGE OF ORLAND PARK 100% VOP 0043	
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	62	62						
20100500	TREE REMOVAL, ACRES	ACRE	0.9	0.9						
20200100	EARTH EXCAVATION	CU YD	12,491		12,491					
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	3,527		3,527					
20400800	FURNISHED EXCAVATION	CU YD	10,938		10,938					
20800150	TRENCH BACKFILL	CU YD	173					151		22
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SO YD	12,990	12,840						150
21101615	TOPSOIL FURNISH AND PLACE, 4"	SO YD	14,970			14,970				
25000210	SEEDING, CLASS 2A	ACRE	0.2			0.2				
25000312	SEEDING, CLASS 4A	ACRE	1.9			1.9				
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	80			80				
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	80			80				
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	80			80				
25100115	MULCH, METHOD 2	ACRE	3.0			3.0				
25100630	EROSION CONTROL BLANKET	SO YD	6,910	6,910						
25200110	SODDING, SALT TOLERANT	SO YD	5,290	5,290						
25200200	SUPPLEMENTAL WATERING	UNIT	224	224						
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	235	235						
28000305	TEMPORARY DITCH CHECKS	FOOT	1,170	1,170						
28000400	PERIMETER EROSION BARRIER	FOOT	4,215	4,215						
28000500	INLET AND PIPE PROTECTION	EACH	7	3						4
28000510	INLET FILTERS	EACH	16	16						
35101800	AGGREGATE BASE COURSE, TYPE B 6"	SO YD	190	190						
35102100	AGGREGATE BASE COURSE, TYPE B 9"	SO YD	150							150
35301200	HIGH-EARLY-STRENGTH PORTLAND CEMENT CONCRETE BASE COURSE 9"	SO YD	635	635						
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	79	64						15
40600300	AGGREGATE (PRIME COAT)	TON	1.4	0.4						1
40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	187.1	80.1				88		19
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	175.7	74.7				88		13
42001300	PROTECTIVE COAT	SO YD	355	355						
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SO FT	8,143	721				3,917		3,505
44000100	PAVEMENT REMOVAL	SO YD	1,442	1,185				257		

• DENOTES SPECIALTY ITEM
 VOP = VILLAGE OF ORLAND PARK

FILE NAME = D:\60N09-SHT-S0001.dgn	USER NAME = TKluegel	DESIGNED - MJT	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.P. RTE. 330	SECTION 2010-135-I	COUNTY COOK	TOTAL SHEETS 101	SHEET NO. 4	
PLOT SCALE = 1:50	CHECKED - TRK	REVISED -	SCALE: N.T.S.			SHEET NO. 1 OF 5 SHEETS	STA. TO STA.	S0-01		CONTRACT NO. 60N09	
PLOT DATE = 1/7/2011	DATE - 12/17/10	REVISED -	ILLINOIS FED. AID PROJECT								