

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE						
				ROADWAY US 45/143RD	TRACK RELOCATION	LANDSCAPING		PLATFORM	VILLAGE OF ORLAND PARK	
				80% FED 20% STATE 0003	80% FED 20% STATE 0021	80% FED 20% STATE 0003		80% FED 20% STATE 0003	100% VOP 0043	
44000300	CURB REMOVAL	FOOT	180							180
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	153	153						
44000600	SIDEWALK REMOVAL	SO FT	9,457	104				8,893		460
44003100	MEDIAN REMOVAL	SO FT	1,215	1,215						
44201741	CLASS D PATCHES, TYPE II, 8 INCH	SO YD	49							49
50101500	REMOVAL OF EXISTING SUPERSTRUCTURES	EACH	1	1						
50102400	CONCRETE REMOVAL	CU YD	274	274						
50157300	PROTECTIVE SHIELD	SO YD	387.0	387.0						
50900805	PEDESTRIAN RAILING	FOOT	180					180		
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	2	1				1		
54213675	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 30"	EACH	1					1		
54247150	GRATING FOR CONCRETE FLARED END SECTION 30"	EACH	1					1		
550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	637.3	544.3				65.0		28
550A0380	STORM SEWERS, CLASS A, TYPE 2 18"	FOOT	25.7	25.7						
550A0430	STORM SEWERS, CLASS A, TYPE 2 30"	EACH	667					667		
550A0450	STORM SEWERS, CLASS A, TYPE 2 36"	FOOT	61.7	61.7						
55100500	STORM SEWER REMOVAL 12"	FOOT	24							24
55100700	STORM SEWER REMOVAL 15"	FOOT	52.1	40.1				12.0		
55100900	STORM SEWER REMOVAL 18"	FOOT	6.0	6.0						
55101400	STORM SEWER REMOVAL 30"	FOOT	954.2	476.2				478.0		
55101600	STORM SEWER REMOVAL 36"	FOOT	26.0	26.0						
56103300	DUCTILE IRON WATER MAIN 12"	FOOT	223							223
56400820	FIRE HYDRANT WITH AUXILIARY VALVE AND VALVE BOX	EACH	1							1
60200805	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 8 GRATE	EACH	2	2						
60201330	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 23 FRAME AND GRATE	EACH	1	1						
60201340	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 24 FRAME AND GRATE	EACH	1	1						
60203805	CATCH BASINS, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	1					1		
60206905	CATCH BASINS, TYPE C, TYPE 1 FRAME, OPEN LID	EACH	2							2
60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	4	4						
60221100	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	2					2		
60221700	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 8 GRATE	EACH	2	2						
60236200	INLETS, TYPE A, TYPE 8 GRATE	EACH	2	2						

• DENOTES SPECIALTY ITEM  
VOP = VILLAGE OF ORLAND PARK

FILE NAME =  
D:\60N09-SHT-50002.dgn

USER NAME = TKIuegl	DESIGNED - MJT	REVISED -
PLOT SCALE = 1:50	DRAWN - MJT	REVISED -
PLOT DATE = 1/7/2011	CHECKED - TRK	REVISED -
	DATE - 12/17/10	REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: N.T.S. SHEET NO. 2 OF 5 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
330	2010-135-1	COOK	101	5
S0-02			CONTRACT NO. 60N09	
ILLINOIS FED. AID PROJECT				