

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE						
				ROADWAY US 45/143RD 80% FED 20% STATE 0003	TRACK RELOCATION 80% FED 20% STATE 0021	LANDSCAPING 80% FED 20% STATE 0003		PLATFORM 80% FED 20% STATE 0003	VILLAGE OF ORLAND PARK 100% VOP 0043	
60237460	INLETS, TYPE A, TYPE 23 FRAME AND GRATE	EACH	1	1						
60250200	CATCH BASINS TO BE ADJUSTED	EACH	1					1		
60255500	MANHOLES TO BE ADJUSTED	EACH	2	1				1		
60500040	REMOVING MANHOLES	EACH	1	1						
60500050	REMOVING CATCH BASINS	EACH	7	2				2		3
60500060	REMOVING INLETS	EACH	1	1						
60600605	CONCRETE CURB, TYPE B	FOOT	226							226
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	124	124						
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	125	125						
60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SO FT	1,150	1,150						
66400105	CHAIN LINK FENCE, 4'	FOOT	305							305
• 66900200	NON-SPECIAL WASTE DISPOSAL	CU YD	5,561	5,561						
• 66900450	SPECIAL WASTE PLANS AND REPORTS	L SUM	1	1						
• 66900530	SOIL DISPOSAL ANALYSIS	EACH	3	3						
X6700410	ENGINEER'S FIELD OFFICE, TYPE A (SPECIAL)	CAL MO	12	12						
67100100	MOBILIZATION	L SUM	1	1						
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	7	7						
73700100	REMOVE GROUND MOUNTED SIGN SUPPORT	EACH	1					1		
• 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	300	300						
• 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	575	575						
• 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	115	115						
• 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	99	99						
• 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	69	69						
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	325							325
* 81017515	CONDUIT IN TRENCH, 1 1/4" DIA., COILABLE NONMETALLIC CONDUIT	FOOT	157					157		
* 81702130	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 6	FOOT	885					885		
* 81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	157					157		
* 83600300	LIGHT POLE FOUNDATION, 30" DIAMETER	FOOT	11					11		
* 84100110	REMOVAL OF TEMPORARY LIGHTING UNIT	EACH	3					3		
* 84200500	REMOVAL OF LIGHTING UNIT, SALVAGE	EACH	13					13		
* 84400105	RELOCATE EXISTING LIGHTING UNIT	EACH	1					1		
• 88600100	DETECTOR LOOP, TYPE I	FOOT	67	67						

• DENOTES SPECIALTY ITEM
 VOP = VILLAGE OF ORLAND PARK

FILE NAME = D160N09-SHT-50003.dgn	USER NAME = TK1uege1	DESIGNED - MJT	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.P. RTE. 330	SECTION 2010-135-1	COUNTY COOK	TOTAL SHEETS 101	SHEET NO. 6	
PLOT SCALE = 1:50	CHECKED - TRK	REVISED -	SCALE: N.T.S.			SHEET NO. 3 OF 5 SHEETS	STA.	TO STA.	SQ-03		CONTRACT NO. 60N09
PLOT DATE = 1/7/2011	DATE - 12/17/10	REVISED -	ILLINOIS FED. AID PROJECT								