

# SUMMARY OF QUANTITIES

CODE	PAY ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE 0031 80% FEDERAL 20% LOCAL
~ * X2080260	TRENCH BACKFILL, SPECIAL	CU YD	40	40
~ * 21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	1,775	1,775
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	35	35
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	35	35
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	35	35
* 25200100	SODDING	SQ YD	1,775	1,775
* 25200200	SUPPLEMENTAL WATERING	UNIT	20	20
~ * 28000510	INLET FILTERS	EACH	30	30
~ 35101600	AGGREGATE BASE COURSE, TYPE B 4"	SQ YD	1,335	1,335
~ 35300100	PORTLAND CEMENT CONCRETE BASE COURSE 6"	SQ YD	475	475
~ 35300300	PORTLAND CEMENT CONCRETE BASE COURSE 8"	SQ YD	325	325
~ 35501287	HOT-MIX ASPHALT BASE COURSE, 2 1/4"	SQ YD	555	555
~ 40300100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	200	200
~ 40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	67	67
~ 40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	125	125
~ 42001300	PROTECTIVE COAT	SQ YD	4,200	4,200
~ 42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	240	240
~ 42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	27,750	27,750
~ 42400800	DETECTABLE WARNINGS	SQ FT	296	296
~ 44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	1,300	1,300
~ 44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	795	795
~ 44000500	COMBINATION CONCRETE CURB AND GUTTER REMOVAL	FOOT	3,900	3,900
~ 44201335	CLASS C PATCHES, TYPE IV, 8 INCH	SQ YD	100	100
~ * 56500600	DOMESTIC WATER SERVICE BOXES TO BE ADJUSTED	EACH	50	50
~ * 56500800	DOMESTIC WATER SERVICE BOXES	EACH	2	2
~ 60265700	VALVE VAULTS TO BE ADJUSTED	EACH	1	1
~ 60266600	VALVE BOXES TO BE ADJUSTED	EACH	2	2
~ 60406000	FRAMES AND LIDS, TYPE 1, OPEN LID	EACH	5	5
~ 60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	5	5
~ 60600605	CONCRETE CURB, TYPE B	FOOT	582	582
* 66900200	NON-SPECIAL WASTE DISPOSAL	CU YD	121	121
* 66900450	SPECIAL WASTE PLANS AND REPORTS	L SUM	1	1
* 66900530	SOIL DISPOSAL ANALYSIS	EACH	1	1
~ 67100100	MOBILIZATION	L SUM	1	1

~ DENOTES SPECIAL PROVISION HAS BEEN PROVIDED  
\* DENOTES SPECIALTY ITEM

CODE	PAY ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE 0031 80% FEDERAL 20% LOCAL
~ 70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1
~ 70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	140	140
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	20	20
* 81018500	CONDUIT PUSHED, 2" DIA., GALVANIZED STEEL	FOOT	500	500
* 81603080	UNIT DUCT, 600V, 3-1C NO.2, 1/C NO.4 GROUND, (XLP-TYPE USE), 1 1/4" DIA. POLYETHYLENE	FOOT	4,800	4,800
* 81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	4,330	3,900
* 83600200	LIGHT POLE FOUNDATION, 24" DIAMETER	FOOT	222	222
~ 550B0320	STORM SEWERS, C' ASS B, TYPE 2 8"	FOOT	30	30
~ 550B0330	STORM SEWERS, CLASS B, TYPE 2 10"	FOOT	80	80
* A2000616	TREE, ACER PLATANOIDES (NORWAY MAPLE), 2" CALIPER, BALLED AND BURLAPPED	EACH	1	1
* B0237345	TREE, PYRUS CALLERYANA CLEVELAND (CLEVELAND SELECT CALLERY PEAR), 2" CALIPER, TREE FORM, BALLED AND BURLAPPED	EACH	8	8
* B2006316	TREE, SYRINGA RETICULATA IVORY SILK (IVORY SILK JAPANESE TREE LILAC), 2" CALIPER, TREE FORM, BALLED AND BURLAPPED	EACH	6	6
~ LR430040	PAVING BRICK SIDEWALK	SQ YD	2,135	2,135
~ * X0323857	EXISTING LIGHT POLE FOUNDATION ADJUSTMENT	EACH	4	4
~ X0326210	GEOTECHNICAL FABRIC, SPECIAL	SQ YD	2,135	2,135
~ * X0326441	STONE BEDDING MATERIAL	TON	500	500
~ * X2111110	TOP SOIL Placement	CU YD	55	55
~ X4404700	SIDEWALK REMOVAL (SPECIAL)	SQ FT	46,965	46,965
~ X6022805	CATCH BASIN, TYPE A, 4' DIAMETER, TYPE 1 FRAME, OPEN LID, SPECIAL	EACH	4	4
~ X6022900	CATCH BASINS TO BE RECONSTRUCTED (SPECIAL)	EACH	1	1
~ X6023204	INLETS, TYPE A, TYPE 1 FRAME, OPEN LID, SPECIAL	EACH	7	7
~ X6025300	CATCH BASINS TO BE ADJUSTED (SPECIAL)	EACH	15	15
~ X6025600	MANHOLES TO BE ADJUSTED (SPECIAL)	EACH	5	5
~ X6028000	MANHOLES TO BE RECONSTRUCTED (SPECIAL)	EACH	2	2
~ X6029600	CATCH BASINS, TYPE C, TYPE 1 FRAME, OPEN LID, SPECIAL	EACH	4	4
~ X6064200	COMBINATION CURB AND GUTTER, TYPE B-6.12 (SPECIAL)	FOOT	3,900	3,900
~ * X8140115	HANDHOLE TO BE ADJUSTED	EACH	3	3
~ Z0018700	DRAINAGE STRUCTURE TO BE REMOVED	EACH	12	12
~ * Z0033028	MAINTENANCE OF LIGHTING SYSTEM	CAL MO	6	6
~ Z0076600	TRAINEES (CONSTRUCTION CODE 0042)	HOUR	500	
~ XX000541	EXPLORATORY EXCAVATION	CU YD	25	25
~ XX000717	STORM SEWER CONNECTION, SPECIAL	EACH	2	2
~ * XX006834	ELECTRICAL CONNECTION TO EXISTING LIGHTING SYSTEM	EACH	4	4
~ XX006993	10" X 4" CATCH BASIN TRAP AND RESTRICTOR	EACH	4	4
~ * XX007151	PLANTER RAILING	FOOT	550	550
~ * XX007152	DECORATIVE LIGHT POLE, ALUMINUM, 12' MOUNTING HEIGHT	EACH	37	37
~ * XX007153	DECORATIVE ACORN STYLE LUMINAIRE, SODIUM VAPOR, TENON MOUNT, 70 WATT	EACH	37	37

Drawing file: \\Projects\76010007 - Grand Ave Streetscape Stage II\4\_SUMM01.dwg Jan 10, 2011 10:02:00am



USER NAME -	DESIGNED - MK	REVISED - 1-5-11 IDOT FINAL
PLOT SCALE -	DRAWN - MK/LEV	REVISED - 6-28-10 IDOT PRE-FINAL
PLOT DATE -	CHECKED - CB	REVISED - 6-04-10 IDOT PSE
	DATE - 03-02-10	REVISED - 3-19-10 MWRDGC

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**GRAND AVENUE STREETSCAPE STAGE II  
SUMMARY OF QUANTITIES**

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1376	10-00095-00-SW	COOK	29	4
(FIELD BOOK NOS. 1441/1443/1516)		CONTRACT NO. 63511		
FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT	TE-00D1(823)	

E.H.E PROJECT NO. 760-10-00720