

SUMMARY OF QUANTITIES

SPECIALTY ITEM	SPECIAL PROVISION	CODE NO.	PAY ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	BRIDGE 0028
		20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	488	488
		20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	130	130
		20101100	TREE TRUNK PROTECTION	EACH	18	18
		20101200	TREE ROOT PRUNING	EACH	10	10
	*	20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	350	350
		20400800	FURNISHED EXCAVATION	CU YD	590	590
		20800150	TRENCH BACKFILL	CU YD	53	53
		21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	1,050	1,050
		21101505	TOPSOIL EXCAVATION AND PLACEMENT	CU YD	515	515
		21101625	TOPSOIL FURNISH AND PLACE, 6"	SQ YD	100	100
S	*	25000115	SEEDING, CLASS 1B	ACRE	1.25	1.25
S		25000400	NITROGEN FERTILIZER NUTRIENT	POUND	100	100
S		25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	100	100
S		25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	100	100
S		25100115	MULCH, METHOD 2	ACRE	2.25	2.25
S		25100630	EROSION CONTROL BLANKET	SQ YD	12,500	12,500
		28000200	EARTH EXCAVATION FOR EROSION CONTROL	CU YD	100	100
		28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	2,920	2,920
	*	28000315	AGGREGATE DITCH CHECKS	TON	6	6
		28000400	PERIMETER EROSION BARRIER	FOOT	2,900	2,900
		28000510	INLET FILTERS	EACH	9	9
		28100107	STONE RIPRAP, CLASS A4	SQ YD	578	578
		28200200	FILTER FABRIC	SQ YD	578	578
		31101200	SUBBASE GRANULAR MATERIAL, TYPE B 4"	SQ YD	206	206
		31101400	SUBBASE GRANULAR MATERIAL, TYPE B 6"	SQ YD	3,194	3,194
		35101600	AGGREGATE BASE COURSE, TYPE B 4"	SQ YD	2,260	2,260
		40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	115	115
		40600300	AGGREGATE (PRIME COAT)	TON	1	1
		40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	260	260
		42001300	PROTECTIVE COAT	SQ YD	190	190
		42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	27	27
		42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	1,611	1,611
		44000100	PAVEMENT REMOVAL	SQ YD	35	35
		44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	27	27
		44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	27	27
		44000600	SIDEWALK REMOVAL	SQ FT	848	848
		44201717	CLASS D PATCHES, TYPE II, 6 INCH	SQ YD	23	23
		50200100	STRUCTURE EXCAVATION	CU YD	793	793
		50300225	CONCRETE STRUCTURES	CU YD	105.9	105.9
		50300280	CONCRETE ENCASEMENT	CU YD	7.8	7.8
	*	50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	12,003	12,003
S	*	50901720	BICYCLE RAILING	FOOT	20	20
	*	51201600	FURNISHING STEEL PILES HP12X53	FOOT	377	377
	*	51202305	DRIVING PILES	FOOT	50	50
	*	51203600	TEST PILE STEEL HP12X53	EACH	1	1

FILE NAME: P:\CIBEL WEST Projects\2009\123140 FoxRvTr-Ph11\G:\vol\Dgr\veh\50001.dgn



USER NAME = #USER#	DESIGNED - DB	REVISED - 10/5/10
PLOT SCALE = N/A	DRAWN - NP	REVISED -
PLOT DATE = 1/4/2011	CHECKED - DB	REVISED -
	DATE - 12/20/10	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**SUMMARY OF
QUANTITIES**

SCALE: N/A SHEET NO. 3 OF 58 SHEETS STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	05-F3000-06-BT	KANE	58	3
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT			CONTRACT NO.63517	