

SUMMARY OF QUANTITIES

SPECIALTY ITEM	SPECIAL PROVISION	CODE NO.	PAY ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	BRIDGE 0028
	*	X7240500	RELOCATE EXISTING SIGNS	EACH	4	4
S	*	XX003067	CONCRETE BRIDGE RAIL (SPECIAL)	FOOT	14	14
	*	XX005913	TEMPORARY ACCESS CAUSEWAY	L SUM	1	1
	*	XX006653	FENCE (SPECIAL)	FOOT	563	563
	*	XX006821	CONCRETE TRUCK WASHOUT	L SUM	1	1
S	*	Z0007124	STEEL RAILING (SPECIAL)	FOOT	21	21
	*	Z0013797	STABILIZED CONSTRUCTION ENTRANCE	SQ YD	291	291
	*	Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1
	*	Z0019600	DUST CONTROL WATERING	UNIT	16	16
	*	Z0021922	SILICONE JOINT SEALER	FOOT	12	12
	*	Z0034210	MECHANICALLY STABILIZED EARTH RETAINING WALL	SQ FT	1,384	1,384
	*	Z0042002	POROUS GRANULAR EMBANKMENT, SUBGRADE	CU YD	350	350
	*	Z0046304	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	59	59
	*	Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1
	*	Z0055905	TEMPORARY CONSTRUCTION FENCE	FOOT	500	500
	*	Z0065000	SETTING PILES IN ROCK	EACH	19	19
	*	Z0076600	TRAINEES	hour	1,000	1,000

△ CONSTRUCTION TYPE CODE: 0042


SCHEDULE OF EARTHWORK

LOCATION	STATUS	21101505		X2020410		66900205		20400800		20201200	
		TOPSOIL EXCAVATION (CU YD)	TOPSOIL EXCAVATION AND PLACEMENT (CU YD)	TOPSOIL EXCAVATION AND DISPOSAL (CU YD)	EARTH EXCAVATION (SPECIAL) (CU YD)	SPECIAL WASTE DISPOSAL (CU YD)	EARTH EXCAVATION ADJUSTED FOR SHRINKAGE (CU YD)	EARTH EMBANKMENT (FILL) (CU YD)	EARTHWORK BALANCE WASTE (+) or SHORTAGE (-) (CU YD)	20042002 ESTIMATED UNSUITABLE (UNDERCUT) (CU YD)	
19+50.00	CLEAR										
19+93.48	CLEAR	32.68		12.47	20.21	0.00	0.00	0.00	61.25	-61.25	0.0
OMIT BRIDGE											
23+71.96	CONTAMINATED										
24+00.00	CONTAMINATED	0.00	14.85	-14.85	180.02	180.02	0.00	1.92	-1.92	0.0	
24+50.00	CONTAMINATED	0.00	42.50	-42.50	532.22	532.22	0.00	0.00	+0.00	0.0	
25+00.00	CONTAMINATED	0.00	37.87	-37.87	424.08	424.08	0.00	0.00	+0.00	0.0	
25+50.00	CONTAMINATED	0.00	32.41	-32.41	317.31	317.31	0.00	0.00	+0.00	0.0	
26+00.00	CONTAMINATED	0.00	23.43	-23.43	183.70	183.70	0.00	0.00	+0.00	0.0	
26+50.00	CONTAMINATED	0.00	9.54	-9.54	70.27	70.27	0.00	0.19	-0.19	0.0	
27+00.00	CONTAMINATED	0.00	4.03	-4.03	42.04	42.04	0.00	0.28	-0.28	0.0	
27+50.00	CONTAMINATED	0.00	4.68	-4.68	41.67	41.67	0.00	0.09	-0.09	0.0	
28+00.00	CONTAMINATED	0.00	2.50	-2.50	36.02	36.02	0.00	0.56	-0.56	0.0	
28+50.00	CONTAMINATED	0.00	0.28	-0.28	28.80	28.80	0.00	3.80	-3.80	0.0	
29+00.00	CONTAMINATED	0.00	2.04	-2.04	31.76	31.76	0.00	4.17	-4.17	0.0	
29+50.00	CONTAMINATED	0.00	1.76	-1.76	32.31	32.31	0.00	2.78	-2.78	0.0	
30+00.00	CONTAMINATED	0.00	0.00	0.00	27.41	27.41	0.00	2.22	-2.22	0.0	
30+50.00	CONTAMINATED	0.00	0.00	0.00	27.04	27.04	0.00	0.46	-0.46	0.0	
31+00.00	CLEAR	27.41	0.00	27.41	3.06	0.00	2.60	0.56	+2.04	0.0	
31+50.00	CLEAR	28.33	0.00	28.33	2.59	0.00	2.20	3.70	-1.50	0.0	
32+00.00	CLEAR	34.81	5.37	29.44	0.09	0.00	0.08	8.24	-8.16	0.0	
32+50.00	CLEAR	46.57	12.96	33.61	0.93	0.00	0.79	10.56	-9.77	0.0	
33+00.00	CLEAR	54.63	17.13	37.50	2.04	0.00	1.73	13.70	-11.97	0.0	
33+50.00	CLEAR	62.41	20.65	41.76	6.02	0.00	5.12	14.44	-9.32	0.0	
34+00.00	CLEAR	58.52	19.26	39.26	6.67	0.00	5.67	7.04	-1.37	0.0	
34+50.00	CLEAR	59.91	21.57	38.34	11.02	0.00	9.37	1.48	+7.89	0.0	
35+00.00	CLEAR	54.35	17.41	36.94	12.41	0.00	10.55	0.93	+9.62	0.0	
35+50.00	CLEAR	43.43	10.19	33.24	5.56	0.00	4.73	1.94	+2.79	0.0	
36+00.00	CLEAR	50.09	15.09	35.00	11.20	0.00	9.52	1.76	+7.76	0.0	
36+50.00	CLEAR	50.00	15.28	34.72	11.85	0.00	10.07	2.87	+7.20	0.0	
37+00.00	CLEAR	45.93	11.48	34.45	4.17	0.00	3.54	6.11	-2.57	0.0	
37+50.00	CLEAR	35.37	5.09	30.28	1.20	0.00	1.02	5.09	-4.07	0.0	
38+00.00	CLEAR	27.31	0.00	27.31	0.00	0.00	0.00	4.17	-4.17	0.0	
38+50.00	CLEAR	27.87	0.00	27.87	0.00	0.00	0.00	5.09	-5.09	0.0	
39+00.00	CLEAR	36.85	5.65	31.20	9.17	0.00	7.79	2.78	+5.01	0.0	
39+50.00	CLEAR	43.15	10.28	32.87	12.41	0.00	10.55	0.37	+10.18	0.0	
40+00.00	CLEAR	38.89	12.04	26.85	3.24	0.00	2.75	10.56	-7.81	0.0	
40+50.00	CLEAR	39.54	17.59	21.95	0.00	0.00	0.00	27.13	-27.13	0.0	
41+00.00	CLEAR	49.72	21.85	27.87	2.41	0.00	2.05	45.74	-43.69	0.0	
41+50.00	CLEAR	51.02	23.61	27.41	2.41	0.00	2.05	72.69	-70.64	0.0	
42+00.00	CLEAR	44.44	24.63	19.81	0.00	0.00	0.00	118.33	-118.33	0.0	
42+50.00	CLEAR	45.37	26.94	18.43	0.00	0.00	0.00	151.67	-151.67	0.0	
43+00.00	CLEAR	23.24	14.26	8.98	0.00	0.00	0.00	77.22	-77.22	0.0	
43+50.00	CLEAR	13.80	0.00	13.80	0.00	0.00	0.00	1.94	-1.94	0.0	
43+60.00	CLEAR	4.17	0.00	4.17	0.09	0.00	0.08	0.39	-0.31	0.0	
43+70.00	CLEAR	2.70	0.00	2.70	0.83	0.00	0.71	0.54	+0.17	0.0	
43+80.00	CLEAR	2.59	0.00	2.59	1.48	0.00	1.28	2.17	-0.91	0.0	
43+90.00	CLEAR	2.59	0.00	2.59	1.48	0.00	1.28	5.70	-4.44	0.0	
43+95.10	CLEAR	1.32	0.00	1.32	0.76	0.00	0.65	3.21	-2.56	0.0	
46+55.10	CLEAR	0.00	0.00	0.00	0.00	0.00	0.00	0.00	+0.00	0.0	
47+00.00	CLEAR	0.00	0.00	0.00	0.00	0.00	0.00	0.00	+0.00	0.0	
47+50.00	CLEAR	4.44	0.00	4.44	0.00	0.00	0.00	0.00	+0.00	0.0	
48+00.00	CLEAR	9.35	0.00	9.35	0.00	0.00	0.00	0.00	+0.00	0.0	
48+42.95	CLEAR	6.68	0.00	6.68	0.00	0.00	0.00	0.00	+0.00	0.0	
STRUCT. EXC.	CONTAMINATED						691.00				
SEWER TRENCHES	CLEAR & CONTAM.						180.00				
EST. UNSUITABLE	CLEAR									350.00	
<b>TOTAL</b>		<b>1,165</b>	<b>515</b>	<b>650</b>	<b>2,095</b>	<b>2,850</b>	<b>95</b>	<b>685</b>	<b>-590</b>	<b>350</b>	

SHRINKAGE FACTOR: 15%

TOTAL: 2,745

FILE NAME = P:\CBBEL\_MEST Projects\2009\123140\_FoxRvrTr-PhH\CV\1\Dgn\hnt\500063.dgn

 <b>WILLS BURKE KELSEY ASSOCIATES LTD.</b> 110 West Main Street, Suite 201 St. Charles, Illinois 60114 (630) 443-7755	USER NAME = #USER#	DESIGNED - DB	REVISED - 10/5/10	<b>STATE OF ILLINOIS</b> <b>DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b> <b>AND SCHEDULE OF EARTHWORK</b>			F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	PLOT SCALE = N/A	DRAWN - NP	REVISED -		05-F3000-06-BT	KANE	58	5				
	PLOT DATE = 1/4/2011	CHECKED - DB	REVISED -		SCALE: N/A SHEET NO. 5 OF 58 SHEETS STA. TO STA.			CONTRACT NO. 63517				
		DATE - 12/20/10	REVISED -		FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT					