

SUMMARY OF QUANTITIES

CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE		
				RESURFACING 0005	SAFETY 0021	TRAINEES 0042
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	450	450	-	-
20800150	TRENCH BACKFILL	CU YD	927	927	-	-
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	3,206	3,206	-	-
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	68	68	-	-
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	68	68	-	-
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	68	68	-	-
25200100	SODDING	SQ YD	3,206	3,206	-	-
25200200	SUPPLEMENTAL WATERING	UNIT	34	34	-	-
28000510	INLET FILTERS	EACH	25	25	-	-
35101400	AGGREGATE BASE COURSE, TYPE B	TON	938	938	-	-
35101600	AGGREGATE BASE COURSE, TYPE B 4"	SQ YD	1,223	1,223	-	-
35102000	AGGREGATE BASE COURSE, TYPE B 8"	SQ YD	1,618	1,618	-	-
35800100	PREPARATION OF BASE	SQ YD	9,684	9,684	-	-
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	4,015	4,015	-	-
40600300	AGGREGATE (PRIME COAT)	TON	41	41	-	-
40600895	CONSTRUCTING TEST STRIP	EACH	1	1	-	-
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	126	126	-	-
40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	1,701	1,701	-	-
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	1,485	1,485	-	-
42001300	PROTECTIVE COAT	SQ YD	1,363	1,363	-	-
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	200	200	-	-
42400800	DETECTABLE WARNINGS	SQ FT	272	272	-	-
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	346	346	-	-
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	1,818	1,818	-	-
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	3,762	3,762	-	-
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	431	431	-	-
550A0160	STORM SEWERS, CLASS A, TYPE 1 36"	FOOT	545	545	-	-
550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	35	35	-	-
550A0360	STORM SEWERS, CLASS A, TYPE 2 15"	FOOT	27	27	-	-
550A0380	STORM SEWERS, CLASS A, TYPE 2 18"	FOOT	18	18	-	-

* INDICATES SPECIALTY ITEM

COPYRIGHT © 2005 BY BAXTER & WOODMAN, INC.
 STATE OF ILLINOIS - PROFESSIONAL DESIGN FIRM
 LICENSE NO. 044-00027 - EXPIRES 4/30/2011
 458622 PM 11/23/2010



DESIGNED - MWP	REVISED - 12-01-10 IDOT REVIEW
DRAWN - KAR	REVISED -
CHECKED - RWL	REVISED -
DATE - 10-01-10	FILE - 041180-500.sh1

**CITY OF COUNTRY CLUB HILLS, ILLINOIS
GLEN OAKS DRIVE INFRASTRUCTURE IMPROVEMENTS**

SUMMARY OF QUANTITIES

SCALE: NONE

STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
-	04-00027-03-PV	COOK	36	4
C-91-004-05		CONTRACT NO. 63539		
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT HPD-897008				