

SUMMARY OF QUANTITIES

CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE		
				RESURFACING 0005	SAFETY 0021	TRAINEES 0042
* 81018700	CONDUIT PUSHED, 3" DIA, GALVANIZED STEEL	FOOT	680	-	680	-
* 81028020	CONDUIT, BORED AND PULLED, COILABLE NON-METALLIC CONDUIT, 3/4"	FOOT	1,418	-	1,418	-
* 81400730	HANDHOLE, COMPOSITE CONCRETE	EACH	3	-	3	-
* 81603000	UNIT DUCT, 600V, 2-1C NO.8, 1/C NO.8 GROUND, (XLP-TYPE USE), 3/4" DIA. POLYETHYLENE	FOOT	685	-	685	-
* 81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	1,283	-	1,283	-
* 82103250	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, PHOTO-CELL CONTROL 250 WATT	EACH	12	-	12	-
* 83006300	LIGHT POLE, ALUMINUM, 30 FT. M.H., 8 FT. MAST ARM	EACH	9	-	9	-
* 83006500	LIGHT POLE, ALUMINUM, 30 FT. M.H., 12 FT. MAST ARM	EACH	3	-	3	-
* 83006500 83006502	LIGHT POLE FOUNDATION, METAL, 11 1/2" Bolt Circle, 8 5/8" x 4"	EACH	12	-	12	-
* 83800505	BREAKAWAY DEVICE, COUPLING, WITH ALUMINUM SKIRT	EACH	12	-	12	-
* 84200500	REMOVAL OF LIGHTING UNIT, SALVAGE	EACH	5	-	5	-
Z0003300	BASE COURSE REMOVAL (SPECIAL)	SQ YD	991	991	-	-
Z0019600	DUST CONTROL WATERING	UNIT	87	87	-	-
Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	182	182	-	-
Z0042002	POROUS GRANULAR EMBANKMENT, SUBGRADE	CU YD	72	72	-	-
Z0056608	STORM SEWER (WATER MAIN REQUIREMENTS) 12 INCH	FOOT	80	80	-	-
Z0076600	TRAINEES	HOUR	500	-	-	500
X2130010	EXPLORATION TRENCH, SPECIAL	FOOT	100	100	-	-
X4240430	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH, SPECIAL	SQ FT	2,672	2,672	-	-
X4240440	PORTLAND CEMENT CONCRETE SIDEWALK 6 INCH, SPECIAL	SQ FT	405	405	-	-
X4401198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	9,684	9,684	-	-
X4404700	SIDEWALK REMOVAL (SPECIAL)	SQ FT	3,077	3,077	-	-
X5538400	STORM SEWERS TO BE CLEANED 30"	FOOT	200	200	-	-
X6022230	MANHOLES, TYPE A, 4'-DIAMETER, WITH SPECIAL FRAME AND GRATE	EACH	1	1	-	-
X6022930	MANHOLES, TYPE A, 5'-DIAMETER, WITH SPECIAL FRAME AND GRATE	EACH	1	1	-	-
X6023204	INLETS, TYPE A, TYPE 1 FRAME, OPEN LID, SPECIAL	EACH	3	3	-	-
X6026050	SANITARY MANHOLES TO BE ADJUSTED	EACH	5	5	-	-
* XX005049	POWER PEDESTALS	EACH	4	-	4	-

* INDICATES SPECIALTY ITEM

COPYRIGHT © 2010 BY BAXTER & WOODMAN, INC.
 STATE OF ILLINOIS - PROFESSIONAL DESIGN FIRM
 LICENSE NO. 184-00197 - EXPIRES 7/30/2011
 12/29/2010 4:58:28 PM I:\C:\Total\ENR\COOK\COMBOS\CADD\SURVEY\DRAWINGS\DOCS\04180-500.sht



DESIGNED - MWP	REVISED - 12-01-10 IDOT REVIEW
DRAWN - KAR	REVISED -
CHECKED - RWL	REVISED -
DATE - 10-01-10	FILE - 041180-500.sht

**CITY OF COUNTRY CLUB HILLS, ILLINOIS
GLEN OAKS DRIVE INFRASTRUCTURE IMPROVEMENTS**

SUMMARY OF QUANTITIES

SCALE: _____ STA. _____ TO STA. _____

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
-	04-00027-03-PV	COOK	36	6
C-91-004-05		CONTRACT NO. 63539		
FED. ROAD DIST. NO. [ILLINOIS] FED. AID PROJECT HPD-897(008)				