



REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT EACH 1

THE FOLLOWING ITEMS SHALL BE REMOVED BY THE CONTRACTOR AND SHALL BE DISPOSED OF BY THEM OUTSIDE THE RIGHT-OF-WAY AT THEIR EXPENSE. THE SALVAGE VALUE OF THE REMOVED EQUIPMENT SHALL BE REFLECTED IN THE CONTRACT BID PRICE.

- 1 EACH TRAFFIC SIGNAL CABINET AND CONTROLLER (COMPLETE)
- 1 EACH FIBER OPTIC PATCH PANEL (COMPLETE)
- 1 EACH MALFUNCTION MANAGEMENT UNIT (COMPLETE)

INSTALL NEW FULL-ACTUATED CONTROLLER AND TYPE IV CABINET, SPECIAL  
INSTALL NEW MANAGED ETHERNET SWITCH, TYPE 1  
SEE FIBER DRAWINGS FOR SPLICE/TERMINATION DETAILS

INSTALL UNINTERRUPTIBLE POWER SUPPLY (SPECIAL KDOT)  
ON EXISTING FOUNDATION

EXISTING POLE

THE TRAFFIC SIGNAL CONTROL EQUIPMENT FOR THIS PROJECT SHALL BE SIEMENS EAGLE COMPATIBLE IN COMPLIANCE WITH THE COUNTY'S EXISTING ATMS