

SPECIALTY ITEMS (Δ)	SPECIAL PROVISION (*)	CODE NUMBER	PAY ITEM DESCRIPTION	UNITS	ROADWAY 80% FEDERAL 20% LOCAL 0005
		40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	2,470
		40600300	AGGREGATE (PRIME COAT)	TON	50
		40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	1,470
	*	40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	350
		40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	2,240
	*	42400800	DETECTABLE WARNINGS	SQ FT	60
	*	44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	24,680
		44000500	COMBINATION CONCRETE CURB AND GUTTER REMOVAL	FOOT	1,000
		44000600	SIDEWALK REMOVAL	SQ FT	3,000
	*	44201741	CLASS D PATCHES, TYPE II, 8 INCH	SQ YD	100
	*	44201745	CLASS D PATCHES, TYPE III, 8 INCH	SQ YD	300
	*	44201747	CLASS D PATCHES, TYPE IV, 8 INCH	SQ YD	300
	*	X6025300	CATCH BASINS TO BE ADJUSTED (SPECIAL)	EACH	10
	*	60250600	CATCH BASINS TO BE ADJUSTED WITH NEW TYPE 3 FRAME AND GRATE	EACH	2
	*	X6026624	VALVE BOXES TO BE ADJUSTED (SPECIAL)	EACH	4
	*	X6030310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	5
	*	60604100	COMBINATION CONCRETE CURB AND GUTTER, TYPE B6.12 (MODIFIED)	FOOT	1,000
		67100100	MOBILIZATION	L SUM	1
		70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1
		70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1
		70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1
		70106800	CHANGEABLE MESSAGE SIGN	CAL MO	2
	*	70300100	SHORT-TERM PAVEMENT MARKING	FOOT	3,890
	*	70300510	PAVEMENT MARKING TAPE, TYPE III - LETTERS AND SYMBOLS	SQ FT	295
	*	70300520	PAVEMENT MARKING TAPE, TYPE III 4"	FOOT	710
	*	70300540	PAVEMENT MARKING TAPE, TYPE III 6"	FOOT	130
	*	70300550	PAVEMENT MARKING TAPE, TYPE III 8"	FOOT	40
	*	70300560	PAVEMENT MARKING TAPE, TYPE III 12"	FOOT	170
	*	70300570	PAVEMENT MARKING TAPE, TYPE III 24"	FOOT	180
Δ		78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	295
Δ		78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	1,940
Δ		78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	2,050
Δ		78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	350
Δ		78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	170
Δ		78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	180
	*	X4240430	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH, SPECIAL	SQ FT	3,000
	*	X6025800	MANHOLES TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID, SPECIAL	EACH	2

COMPANY NAME: SEC Group, Inc.
 CLIENT: City of Aurora
 DATE PLOTTED: 1/13/2011 9:35:37 AM
 FILE NAME: 86100291-500.dgn
 PLOT DRIVER: PLOTDRIVER
 STANDING TRANSFER

SEC Group, Inc.
 420 N. First Street
 Aurora, IL 60005-2708
 1-815-236-1778 • 616-266-1781
 www.secgroup.com

USER NAME = JSr2xal	DESIGNED - JJS	REVISED -
FILE NAME = 86100291-500.dgn	DRAWN - SMP	REVISED -
PLOT SCALE = NA	CHECKED - AC	REVISED -
PLOT DATE = 1/13/2011	DATE -	REVISED -

CITY OF AURORA

**SULLIVAN ROAD
 SUMMARY OF QUANTITIES**

SCALE: NA SHEET NO. 1 OF 1 SHEETS STA. NA TO STA. NA

F.A. RTE. 1502	SECTION 10-00291-00-RS	COUNTY KANE	TOTAL SHEETS 15	SHEET NO. 3
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT			CONTRACT NO. 63543	