

SUMMARY OF QUANTITIES

SI	CODE NO.	ITEM	UNIT	QUANTITY	ROADWAY	71st STREET BRIDGE SN 016-7721	WALLS SN 016-7726 THRU SN 016-7726	TRANEES	71st STREET LIFT STATION
					0004	0008	0040	0042	0043
*	56100700	WATER SERVICE MAIN 8"	FOOT	50	50				
*	56200300	WATER SERVICE LINE 1"	FOOT	96	96				
*	56200700	WATER SERVICE LINE 2"	FOOT	32	32				
*	56300300	ADJUSTING WATER SERVICE LINES	FOOT	60	60				
*	56400500	FIRE HYDRANTS TO BE REMOVED	EACH	4	4				
*	56400820	FIRE HYDRANT WITH AUXILIARY VALVE AND VALVE BOX	EACH	7	7				
	58000100	MEMBRANE WATERPROOFING	SQ FT	4,602	0	4,602			
	59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	3,055	0	367	2,688		
	60107600	PIPE UNDERDRAINS 4"	FOOT	440	440				
	60108100	PIPE UNDERDRAINS 4" (SPECIAL)	FOOT	48	48				
	60200205	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	1				
	60200805	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 8 GRATE	EACH	3	3				
	60201205	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 12 FRAME AND GRATE	EACH	30	30				
	60201340	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 24 FRAME AND GRATE	EACH	3	3				
	60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	17	17				
	60221100	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	12	11				1
	60223800	MANHOLES, TYPE A, 6'-DIAMETER, TYPE 1FRAME, CLOSED LID	EACH	1	1				
	60236200	INLETS, TYPE A, TYPE 8 GRATE	EACH	2	2				
	60236900	INLETS, TYPE A, TYPE 12 FRAME AND GRATE	EACH	20	20				
	60240315	INLETS, TYPE B, TYPE 12 FRAME AND GRATE	EACH	2	2				
	60250500	CATCH BASINS TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	2	2				
	60500040	REMOVING MANHOLES	EACH	17	17				
	60500050	REMOVING CATCH BASINS	EACH	22	22				
	60500060	REMOVING INLETS	EACH	2	2				
	60600605	CONCRETE CURB, TYPE B	FOOT	620	620				
	60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	5,300	5,300				
	60619200	CONCRETE MEDIAN, TYPE SB-6.06	SQ FT	182	182				
*	66400305	CHAIN LINK FENCE, 6'	FOOT	914	914				
*	66400505	CHAIN LINK FENCE, 8'	FOOT	281	45				236
*	66407600	CHAIN LINK GATES, 6' X 12' DOUBLE	EACH	1	1				
*	66407900	CHAIN LINK GATES, 6' X 18' DOUBLE	EACH	1	1				
*	66900205	SPECIAL WASTE DISPOSAL	CU YD	98	98				
	67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	18	18				
	67100100	MOBILIZATION	L SUM	1	1				
	70106800	CHANGEABLE MESSAGE SIGN	CAL MO	24	24				
*	70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	6,400	6,400				
*	70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	90	90				
	70400100	TEMPORARY CONCRETE BARRIER	FOOT	1,600	1,600				

* DENOTES SPECIALTY ITEM

FILE NAME = F:\A60156677\000_CAD\001_Drawings\Sheets\Civil\06155877-Int-S00-03.dgn



USER NAME = manrj	DESIGNED - NJH	REVISED -
PLOT SCALE = 1.000' / IN.	DRAWN - NJH	REVISED -
PLOT DATE = 1/20/2011	CHECKED - TJW	REVISED -
	DATE - JANUARY 7, 2010	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SCALE: NONE SHEET NO. 3 OF 6 SHEETS STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1537	06-00050-00-GS	COOK	209	6
FED. ROAD DIST. NO. 1 ILLINOIS			CONTRACT NO. 63556	
FED. AID PROJECT CRE-90031709				