

SUMMARY OF QUANTITIES

SI	CODE NO.	ITEM	UNIT	QUANTITY	ROADWAY	71st STREET BRIDGE SN 016- 7721	WALLS SN 016- 7722 THRU SN016- 7726	TRAINEES	71st STREET LIFT STATION
					0004	0008	0040	0042	0043
	70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	3,200	3,200				
	72000100	SIGN PANEL - TYPE 1	SQ FT	103	103				
	72000200	SIGN PANEL - TYPE 2	SQ FT	26	26				
	72400310	REMOVE SIGN PANEL - TYPE 1	SQ FT	49	49				
	72400320	REMOVE SIGN PANEL - TYPE 2	SQ FT	16	16				
	72400710	RELOCATE SIGN PANEL - TYPE 1	SQ FT	30	30				
	72400720	RELOCATE SIGN PANEL - TYPE 2	SQ FT	14	14				
	73400100	CONCRETE FOUNDATIONS	CU YD	10.2	0				10.2
*	78003110	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 4"	FOOT	5,839	5,839				
*	78003130	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 6"	FOOT	1,562	1,562				
*	78003180	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 24"	FOOT	107	107				
*	81000700	CONDUIT IN TRENCH, 2 1/2" DIA., GALVANIZED STEEL	FOOT	445	445				
*	81100600	CONDUIT ATTACHED TO STRUCTURE, 2" DIA., GALVANIZED STEEL	FOOT	360	360				
*	81101000	CONDUIT ATTACHED TO STRUCTURE, 4" DIA., GALVANIZED STEEL	FOOT	240	0	240			
*	81300530	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 12" X 10" X 6"	EACH	6	6				
*	81300730	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 16" X 14" X 6"	EACH	4	4				
*	81603050	UNIT DUCT, 600V, 3-1C NO.6, 1/C NO.8 GROUND, (XLP-TYPE USE), 1" DIA. POLYETHYLENE	FOOT	1,625	1,625				
*	81702415	ELECTRIC CABLE IN CONDUIT, 600V(XLP-TYPE USE) 3-1C NO. 6	FOOT	415	415				
*	81800330	AERIAL CABLE, 3-1C NO. 6 WITH MESSENGER WIRE	FOOT	3,025	3,025				
*	81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	3,005	3,005				
*	82102250	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 250 WATT	EACH	12	12				
*	82107200	UNDERPASS LUMINAIRE, 100 WATT, HIGH PRESSURE SODIUM VAPOR	EACH	6	6				
*	83057285	LIGHT POLE, WOOD, 50 FOOT, CLASS 3, WITH 15FT MAST ARM	EACH	12	12				
*	83600200	LIGHT POLE FOUNDATION, 24" DIAMETER	FOOT	80	80				
*	X0310215	LIGHT POLE FOUNDATION, 24" DIAMETER, OFFSET	FOOT	16	16				
*	84100110	REMOVAL OF TEMPORARY LIGHTING UNIT	EACH	12	12				
*	84200500	REMOVAL OF LIGHTING UNIT, SALVAGE	EACH	12	12				
*	84200804	REMOVAL OF POLE FOUNDATION	EACH	12	12				
*	B2005138	TREE, MALUS SPRING SNOW (SPRING SNOW CRABAPPLE), 3" CALIPER, TREE FORM, BALLED AND BURLAPPED	EACH	13	13				
*	C2001636	SHRUB, CORNUS SERICEA (REDOsier DOGWOOD), 3' HEIGHT, BALLED AND BURLAPPED	EACH	50	50				
*	K1005481	SHREDDED BARK MULCH 3"	SQ YD	80	80				
*	Z0033028	MAINTENANCE OF LIGHTING SYSTEM	CAL MO	18	18				
	X0324455	DRILLING AND SETTING SOLDIER PILES (IN SOIL)	CU FT	4,614	0		4,614		
	X0324546	MANHOLE, SPECIAL, FRAME AND LID	EACH	1	1				
	X0324634	REMOVE, STOCKPILE, AND REPLACE SIGN PANEL AND SIGN PANEL ASSEMBLY (SPECIAL)	EACH	1	1				
	X0325003	REMOVE EXISTING VALVE AND VAULT	EACH	1	1				
	X0326033	GUARD HOUSE REMOVAL AND REPLACEMENT	L SUM	1	1				

* DENOTES SPECIALTY ITEM

FILE NAME = P:\60155677-000_CAD_001_Drawing\Sheets\Civil\60155677-rat-500-01.dgn



USER NAME = manuj	DESIGNED - NJH	REVISED -
PLOT SCALE = 1/800' / IN.	DRAWN - NJH	REVISED -
PLOT DATE = 1/20/2011	CHECKED - TJW	REVISED -
	DATE - JANUARY 7, 2010	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SCALE: NONE SHEET NO. 4 OF 6 SHEETS STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1537	06-00050-00-GS	COOK	209	7
CONTRACT NO. 63556				
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT CRE-90031709				