

# SUMMARY OF QUANTITIES

SI	CODE NO.	ITEM	UNIT	QUANTITY	ROADWAY	71st STREET BRIDGE SN 016-7721	WALLS SN 016-7722 THRU SN 016-7726	TRAINEES	71st STREET LIFT STATION
					0004	0008	0040	0042	0043
	Z0007118	UNTREATED TIMBER LAGGING	SQ FT	24,189	0		24,189		
	Z0018911	DRILL AND GROUT #6 TIE BARS	EACH	52	52				
	Z0022800	FENCE REMOVAL	FOOT	1,569	1,362				207
	Z0026404	FURNISHING SOLDIER PILES (W SECTION)	FOOT	7,361	0		7361		
	Z0030275	IMPACT ATTENUATORS, TEMPORARY (SEVERE USE, NARROW), TEST LEVEL 2	EACH	2	2				
	Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	379	379				
	Z0042002	POROUS GRANULAR EMBANKMENT, SUBGRADE	CU YD	100	100				
	Z0046304	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	1,879	0	156	1,723		
	Z0048865	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1				
	Z0048900	RAILROAD TRACK REMOVAL	FOOT	28	28				
	Z0056608	STORM SEWER (WATER MAIN REQUIREMENTS) 12 INCH	FOOT	231	231				
	Z0056610	STORM SEWER (WATER MAIN REQUIREMENTS) 15 INCH	FOOT	76	76				
	Z0062456	TEMPORARY PAVEMENT	SQ YD	800	800				
	Z0073002	TEMPORARY SOIL RETENTION SYSTEM	SQ FT	800	0	800			
△	Z0076600	TRAINEES	HOUR	2,000	0			2,000	
	<del>XX008495</del>	<del>STORM SEWER JACKED IN PLACE 84" (SPECIAL)</del>	<del>FOOT</del>	<del>128</del>	<del>128</del>				
*	<del>XX008496</del>	<del>LIFT STATION</del>	<del>L SUM</del>	<del>1</del>	<del>1</del>				
*	<del>XX008497</del>	<del>CHECK VALVE 12"</del>	<del>EACH</del>	<del>3</del>	<del>0</del>				<del>3</del>
*	<del>XX008498</del>	<del>CARBON STEEL FORCE MAIN, 12"</del>	<del>FOOT</del>	<del>60</del>	<del>0</del>				<del>60</del>
*	<del>XX008499</del>	<del>8" VALVE IN 48" DIA. VALVE VAULT, TYPE 1 FRAME, CLOSED LID</del>	<del>EACH</del>	<del>3</del>	<del>3</del>				
*	<del>XX008500</del>	<del>8" VALVE IN VALVE BOX</del>	<del>EACH</del>	<del>1</del>	<del>1</del>				
*	<del>XX008501</del>	<del>16" VALVE IN VALVE BOX</del>	<del>EACH</del>	<del>1</del>	<del>1</del>				
*	<del>XX008502</del>	<del>16"X8" REDUCING TAPPING SLEEVE AND 8" DIA. GATE VALVE IN 6 FT-DIA. VALVE VAULT, TYPE 1 FRAME, CLOSED LID</del>	<del>EACH</del>	<del>1</del>	<del>1</del>				
	<del>XX008503</del>	<del>CONSTRUCTION OF JUMP SPANS</del>	<del>L SUM</del>	<del>1</del>	<del>0</del>	<del>1</del>			
*	<del>81603598</del>	<del>UNIT DUCT, 600V, 6-1/C NO. 6, 1/C NO. 8 GROUND, (XLP-TYPE USE), 1 1/2" POLYETHYLENE</del>	<del>FOOT</del>	<del>1,525</del>	<del>1,525</del>				
	<del>X5500320</del>	<del>PRECAST TRANSITION PIPE, 36" TO 84" DIAMETER STORM SEWER</del>	<del>EACH</del>	<del>1</del>	<del>1</del>				
	<del>X5500330</del>	<del>PRECAST TRANSITION PIPE, 78" TO 84" DIAMETER STORM SEWER</del>	<del>EACH</del>	<del>1</del>	<del>1</del>				
	<del>XX008504</del>	<del>PRECAST "T" MANHOLES FOR 78" DIAMETER STORM SEWER, TYPE 1 FRAME, CLOSED LID</del>	<del>EACH</del>	<del>1</del>	<del>1</del>				
	<del>XX008505</del>	<del>PRECAST "T" MANHOLES FOR 84" DIAMETER STORM SEWER, TYPE 1 FRAME, CLOSED LID</del>	<del>EACH</del>	<del>3</del>	<del>3</del>				

△ = 0042

\* DENOTES SPECIALTY ITEM

FILE NAME = P:\G0158877-2009\_CAD\001\_Drawing\Sheet\Civil\60158877-sht-500-06.dgn



USER NAME = manuj	DESIGNED - NJH	REVISED -
PLOT SCALE = 1:800' / IN.	DRAWN - NJH	REVISED -
PLOT DATE = 1/20/2011	CHECKED - TJW	REVISED -
	DATE - JANUARY 7, 2010	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**SUMMARY OF QUANTITIES**

SCALE: NONE      SHEET NO. 6 OF 6 SHEETS      STA.      TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1537	06-00050-00-GS	COOK	209	9
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT			CONTRACT NO. 63556	
CRE-9003(709)				