

# SCHEDULE OF QUANTITIES

ITEM NO.	DESCRIPTION	UNIT	LOCATION	TO	FROM	REMARKS
20100110	TREE REMOVAL (6 TO 15 DIAMETER UNITS)					
		8	STA. 68 + 79	45.1'	RT	
		8	STA. 68 + 80	49.1'	RT	
		8	STA. 68 + 86	67'	LT	
		8	STA. 69 + 5	44.1'	RT	
		6	STA. 69 + 22	46'	LT	
		10	STA. 69 + 36	61.5'	LT	
		48	TOTAL			
20100210	TREE REMOVAL (OVER 15 DIAMETER UNITS)					
		16	STA. 68 + 71	76.6'	RT	
		18	STA. 69 + 5	57.5'	RT	
		20	STA. 69 + 12	48.7'	RT	
		54	TOTAL			
20200100	EARTH EXCAVATION	CU YD	LOCATION			
		110	LT & RT STA. 68 + 31		TO 70 + 0	
		110	TOTAL			
20200200	ROCK EXCAVATION	CU YD	LOCATION			
		20	LT & RT STA. 69 + 0			REMARK'S Possible excavation under proposed Box Culvert
		20	TOTAL			
25100630	EROSION CONTROL BLANKET	SQ YD	LOCATION			
		438.0	LT. STA. 68 + 75		TO 70 + 0	
		438.0	TOTAL			
25200110	SODDING, SALT TOLERANT	SQ YD	LOCATION			
		278.0	RT. STA. 67 + 77		TO 69 + 27	
		278.0	TOTAL			
25200200	SUPPLEMENTAL WATERING	UNIT	LOCATION			
		13.0	LT. STA. 67 + 77		TO 69 + 27	
		13.0	TOTAL			
28000305	TEMPORARY DITCH CHECKS	FOOT	LOCATION			
		20	LT. STA. 69 + 50			
		20	TOTAL			
28000400	PERIMETER EROSION BARRIER	FOOT	LOCATION			
		145	RT STA. 69 + 58		TO 69 + 28	
		26	LT STA. 68 + 77		TO 69 + 3	
		171	TOTAL			
28000500	INLET AND PIPE PROTECTION	EACH	LOCATION			
		1	LT. STA. 69 + 0			
		1	TOTAL			
28100107	STONE RIPRAP, CLASS A4	SQ YD	LOCATION			
		68.0	LT. STA. 69 + 0			
		79.0	RT. STA. 69 + 0			
		147.0	TOTAL			

28200200	FILTER FABRIC	SQ YD	LOCATION			
		470.0	LT & RT STA. 69 + 0			
		470.0	TOTAL			
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	LOCATION			
		71.0	LT & RT STA. 68 + 31		TO 69 + 27	
		71.0	TOTAL			
42300300	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 7"	SQ YD	LOCATION			
		56.0	RT STA. 68 + 50			
		56.0	TOTAL			
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	LOCATION			
		214.0	LT & RT STA. 68 + 31		TO 68 + 74	
		214.0	TOTAL			REMARK'S Includes shoulder and 2nd Ave.
44000400	GUTTER REMOVAL	FOOT	LOCATION			
		29	RT STA. 68 + 31		TO 68 + 60	
		20	RT STA. 69 + 6		TO 69 + 26	
		49	TOTAL			
44201383	CLASS C PATCHES, TYPE IV, 12 INCH	SQ YD	LOCATION			
		155.0	CL STA. 68 + 74		TO 69 + 27	
		155.0	TOTAL			
48101200	AGGREGATE SHOULDERS, TYPE B	TON	LOCATION			
		32.0	LT STA. 68 + 31		TO 70 + 0	
		32.0	TOTAL			
50100300	REMOVAL OF EXISTING STRUCTURES NO. 1	EACH	LOCATION			
		1	STA. 69 + 0			REMARK'S 12x6 Concrete Box Culvert
		1	TOTAL			
51500100	NAME PLATES	EACH	LOCATION			
		1	69 + 0			REMARK'S SN 081-1129
		1	TOTAL			
54010805	PRECAST CONCRETE BOX CULVERTS 8' X 5'	FOOT	LOCATION			
		146	69 + 0			REMARK'S
		146	TOTAL			
60600095	CLASS SI CONCRETE OULET	CU YD	LOCATION			
		2	RT. STA. 68 + 95			REMARK'S OUTLET OVER CULVERT
		2	TOTAL			
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	LOCATION			
		88	RT. STA. 68 + 31		TO 69 + 27	
		88	TOTAL			REMARK'S