

ENTRANCE & EARTHWORK SCHEDULE

ENTRANCE SCHEDULE

STATIONING	REMARKS	35101400		40600200	40800050	
		PROPOSED SURFACE AREA	PROPOSED AGGREGATE AREA	AGGREGATE BASE COURSE, TYPE B	BITUMINOUS MATERIALS (PRIME COAT)	INCIDENTAL HOT-MIX ASPHALT SURFACING
		SQ. YD.	SQ. YD.	TON	TON	TON
US BUS 20						
121+25	RT CE	153.6	163.7	74.6	0.22	21.5
129+68	LT PE	71.6	83.0	37.8	0.10	10.0
131+83	LT PE	105.6	121.8	55.5	0.15	14.8
134+62	RT CE	141.6	151.6	69.1	0.20	19.8
136+50	LT PE	78.2	89.2	40.6	0.11	11.0
ANDERSON DR.						
48+19	LT CE	110.7	119.0	54.2	0.16	15.5
48+57	RT CE	110.2	116.8	53.2	0.16	15.4
GRAND TOTAL				385.0	1.1	108.0

EARTH WORK SCHEDULE

LOCATION	EARTH EXC (CUT)	EARTH EXC ADJ SHRINK 25%	EMBANK (FILL)	EARTH WORK BALANCE WASTE (+) SHORTAGE (-)
	CU YD	CU YD	CU YD	CU YD
US Bus 20				
120+20 - 133+00	2497	1873	1873	0
133+00 - 139+52	851	638	489	149
Anderson Dr.				
47+00 - 49+50	182	137	36	101
TOTAL	3530	2648	2398	250