

GENERAL NOTES

The final top four inches of soil in any right-of-way area disturbed by the Contractor must be capable of supporting vegetation. The soil must be from the A horizon (zero to 2' deep) of soil profiles of local soils.

All Borrow/Waste/Use sites must be approved by the Department prior to removing any material from the project or initiating any earthmoving activities, including temporary stockpiling outside the limits of construction.

The Contractor shall seed all disturbed areas within the project limits. Seeding Class 4 or 2A shall be used, except in front of properties where the grass will be mowed, then use Seeding, Class 1. Class 2A shall be used on front slopes and ditch bottoms. Class 4 shall be used behind Type A gutter, on all backslopes and areas behind the backslope, and beyond the toe of front slope on fill sections without ditches. This work will be included in the contract unit price per Cubic Yard for CONCRETE REMOVAL.

Fertilizer shall be applied to all disturbed areas and incorporated into the seedbed prior to seeding or placement of sod at the rate specified in Sections 250 and 252 of the Standard Specifications. This work shall be included in the cost of CONCRETE REMOVAL.

Mulch Method II shall be applied over all seeded areas. This shall be included in the cost of the CONCRETE REMOVAL.

The Contractor shall be responsible for protecting utility property during construction operations as outlined in Article 107.31 of the Standard Specifications. A minimum of 48 hours advance notice is required for non-emergency work. The JULIE number is 800-892-0123.

STANDARDS

- 701006-03 Off-Road Operations, 2L, 2W, 4.5 m (15') to 600 mm (24") From Pavement Edge
- 701301-04 Lane Closure, 2L, 2W, Short Time Operations
- 701501-06 Urban Lane Closure, 2L, 2W, Undivided
- 701801-04 Lane Closure, Multilane 1W or 2W Crosswalk or Sidewalk Closure
- 701316-05 Lane Closure, 2L, 2W, Bridge Repair, for Speeds > 45 MPH
- 701901-01 Traffic Control Devices
- 720011-01 Metal Posts for Signs, Markers and Delineators
- 728001-01 Telescoping Steel Sign Support
- 729001-01 Applications of Types A and B Metal Posts (For Signs & Markers)

INDEX OF SHEETS

1. Cover Sheet
2. Summary of Quantities
3. General Notes, Standards, Index of Sheets
- 4.-5. Traffic Control Plan
- 6.-10. Culvert Repair Plans

FILE NAME =	USER NAME = lmkdj	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	GENERAL NOTES, STANDARDS, INDEX OF SHEETS	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
D:\BR\CADD plans\Ogle County\8711823\PL	Weng.dgn	DRAWN -	REVISED -			549	117M	OGLE	10	3	
PLOT SCALE = 58.0000' / IN.		CHECKED -	REVISED -			CONTRACT NO. 64C84					
PLOT DATE = Fri Feb 04 13:32:27 2011		DATE -	REVISED -			ILLINOIS FED. AID PROJECT					
						SCALE: _____	SHEET NO. ___ OF ___ SHEETS	STA. _____ TO STA. _____			