

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTR. CODE
				STATE FUNDS
				100% STATE
				STRUCTURE
				0014
				RURAL
20200500	EARTH EXCAVATION (WIDENING)	CU YD	200	200
28100107	STONE RIPRAP, CLASS A4	SO YD	266	266
28200200	FILTER FABRIC	SO YD	347	347
28300400	AGGREGATE DITCH	TON	81	81
35600724	HOT-MIX ASPHALT BASE COURSE WIDENING, 12"	SO YD	598	598
50102400	CONCRETE REMOVAL	CU YD	11	11
50300225	CONCRETE STRUCTURES	CU YD	6.8	6.8
50300255	CONCRETE SUPERSTRUCTURE	CU YD	4.2	4.2
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	2100	2100
50800515	BAR SPLICERS	EACH	26	26
52000110	PREFORMED JOINT STRIP SEAL	FOOT	86	86
67100100	MOBILIZATION	L SUM	1	1
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1	1
70400100	TEMPORARY CONCRETE BARRIER	FOOT	407	407
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	358	358
• 78001110	PAINT PAVEMENT MARKING - LINE 4 "	FOOT	707	707
• 78001130	PAINT PAVEMENT MARKING - LINE 6 "	FOOT	175	175
78300100	PAVEMENT MARKING REMOVAL	SO FT	582	582
X0323265	REMOVE EXISTING RIPRAP	SO YD	87	87
X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1
X7200201	WIDTH RESTRICTION SIGNING	L SUM	1	1
Z0016200	DECK SLAB REPAIR (PARTIAL)	SO YD	50	50
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON- REDIRECTIVE), TEST LEVEL 3	EACH	2	2
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON- REDIRECTIVE), TEST LEVEL 3	EACH	2	2

• SPECIALITY ITEMS