

SUMMARY OF QUANTITIES

URBAN
100% STATE

CODE NO	ITEM	UNIT	CONSTR CODE
			0031
			TOTAL QUANTITY
25000750	MOWING	ACRE	171.5
25100115	MULCH, METHOD 2	ACRE	24.5
28000400	PERIMETER EROSION BARRIER	FOOT	2050
67100100	MOBILIZATION	L SUM	1
C2C02024	SHRUB, CORYLUS AMERICANA (AMERICAN FILBERT), 2' HEIGHT, CONTAINER	EACH	600
C2C12424	SHRUB, VIBURNUM LENTAGO (NANNYBERRY VIBURNUM), 2' HEIGHT, CONTAINER	EACH	600
F30040Y2	SEEDLING-CARYA OVATA (SHAGBARK HICKORY), 2-YEAR OLD, BARE ROOT	UNIT	5
F30120Y2	SEEDLING-QUERCUS ALBA (WHITE OAK), 2-YEAR OLD, BARE ROOT	UNIT	5
F30140Y2	SEEDLING-QUERCUS MACROCARPA (BUR OAK), 2-YEAR OLD, BARE ROOT	UNIT	5
F30160Y2	SEEDLING-QUERCUS RUBRA (RED OAK), 2-YEAR OLD, BARE ROOT	UNIT	5
F30210Y2	SEEDLING-AMELANCHIER CANADENSIS(SHADBLOW SERVICEBERRY), 2-YEAR OLD, BARE ROOT	UNIT	5
F30090Y2	SEEDLING-OSTRYA VIRGINIANA (AMERICANHOPHORNBEAM), 2-YEAR OLD, BARE ROOT	UNIT	5
K1005421	SEEDING (SPECIAL)	ACRE	24.5
X0324840	DISKING	ACRE	24.5

GENERAL NOTES

SEEDING SHALL NOT BE PERMITTED AT ANY TIME WHEN THE GROUND IS FROZEN, WET, OR IN AN UNTILLABLE CONDITION. LOCATIONS TO BE SEEDED WILL BE DETERMINED BY THE ENGINEER.

ONLY THOSE TREES DESIGNATED BY THE ENGINEER OR LISTED IN THE TREE REMOVAL SCHEDULE SHALL BE REMOVED. THE CONTRACTOR SHALL PROTECT ALL REMAINING TREES FROM DAMAGE DUE TO HIS OPERATIONS.

ABANDONED UNDERGROUND UTILITIES THAT CONFLICT WITH CONSTRUCTION SHALL BE DISPOSED OF OUTSIDE THE LIMITS OF THE RIGHT OF WAY ACCORDING TO ARTICLE 202.03 OF THE STANDARD SPECIFICATIONS AND AS DIRECTED BY THE ENGINEER. THIS WORK WILL NOT BE PAID FOR SEPARATELY, BUT SHALL BE INCLUDED IN THE COST OF THE DISKING.

ANY REFERENCE TO A STANDARD IN THESE PLANS SHALL BE INTERPRETED TO MEAN THE EDITION AS INDICATED BY THE SUBNUMBER SHOWN IN THE LIST OF STANDARDS OR THE COPY INCLUDED IN THESE PLANS.

THE CONTRACTOR SHALL CONTACT JULIE AT LEAST 48 HOURS PRIOR TO DISKING OR EXCAVATION TO DETERMINE WHICH UTILITIES ARE IN THE AREA.

PLANTS SHALL BE PLANTED 15 FEET CENTER-TO-CENTER

ALL SOILS DISTURBED BY ANY CONSTRUCTION OPERATION SHALL BE LEFT ON, AND INCORPORATED WITHIN, THE PROJECT LIMITS.

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION
DISTRICT THREE

PREPARED BY: Don Brown
DISTRICT STUDIES & PLANS ENGINEER

DATE: 1-12-11

EXAMINED BY: [Signature]
DISTRICT CONSTRUCTION ENGINEER

[Signature]
DISTRICT MATERIALS ENGINEER

[Signature]
DISTRICT OPERATIONS ENGINEER

FILE NAME =	USER NAME = verdinemi	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES AND GENERAL NOTES				F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
ct:\pwwork\pwwork\verdine\1\0235064\036667-sht-cover.dgn		DRAWN -	REVISED -		319	(45-1)I	KANE	4	2				
PLOT SCALE = 50.0000' / IN.		CHECKED -	REVISED -		SCALE: SHEET NO. OF SHEETS STA. TO STA.				CONTRACT NO. 66A67				
PLOT DATE = Jan 11, 2011 - 11:03:51 AM		DATE -	REVISED -		ILLINOIS FED. AID PROJECT								