

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL		
			FEDERAL - STATE 80% - 20%	ROADWAY 0004	CULVERT 0011 (055-2008)
20100500	TREE REMOVAL, ACRES	ACRE	0.25	0.25	----
20200100	EARTH EXCAVATION	CU YD	2263	2263	----
20200500	EARTH EXCAVATION (WIDENING)	CU YD	356	356	----
20400800	FURNISHED EXCAVATION	CU YD	510	510	----
20700220	POROUS GRANULAR EMBANKMENT	CU YD	95	---	95
20800150	TRENCH BACKFILL	CU YD	762	762	----
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	1,030	---	1,030
21101615	TOP SOIL FURNISH AND PLACE, 4"	SQ YD	3576	3576	----
* 25000300	SEEDING, CLASS 3	ACRE	0.74	0.74	----
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	67	67	----
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	67	67	----
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	67	67	----
* 25100115	MULCH, METHOD 2	ACRE	0.74	0.74	----
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	200	200	----
28000305	TEMPORARY DITCH CHECKS	FOOT	300	300	----
28000400	PERIMETER EROSION BARRIER	FOOT	400	400	---
28100105	STONE RIPRAP, CLASS A3	SQ YD	237	237	---
28100109	STONE RIPRAP, CLASS A5	SQ YD	263	---	263
28200200	FILTER FABRIC	SQ YD	741	---	741
31100910	SUB BASE GRANULAR MATERIAL, TYPE A 12"	SQ YD	1050	1050	---

CODE NO.	ITEM	UNIT	TOTAL		
			FEDERAL - STATE 80% - 20%	ROADWAY 0004	CULVERT 0011 (055-2008)
35501324	HOT-MIX ASPHALT BASE COURSE, 10"	SQ YD	879	879	---
35600716	HOT-MIX ASPHALT BASE COURSE WIDENING, 10"	SQ YD	203	203	---
40600215	POLYMERIZED BITUMINOUS MATERIALS (PRIME COAT)	TON	1	1	---
40600300	AGGREGATE (PRIME COAT)	TON	6	6	---
40600825	POLYMERIZED LEVELING BINDER (MACHINE METHOD), N50	TON	70	70	---
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	240	240	---
40600990	TEMPORARY RAMP	SQ YD	27	27	----
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	160	160	----
44000100	PAVEMENT REMOVAL	SQ YD	140	140	----
44000152	HOT-MIX ASPHALT SURFACE REMOVAL, 3/4"	SQ YD	1668	1668	----
48101200	AGGREGATE SHOULDERS, TYPE B	TON	30	30	----
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1	----	1
50200100	STRUCTURE EXCAVATION	CU YD	432	---	432
50200450	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL FOR STRUCTURES	CU YD	605	---	605
50800105	REINFORCEMENT BARS	POUND	83,790	----	83,790
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	960	---	960
50800515	BAR SPLICERS	EACH	120	---	120
51500100	NAME PLATES	EACH	1	----	1
54003000	CONCRETE BOX CULVERTS	CU YD	393.2	----	393.2
63200310	GUARDRAIL REMOVAL	FOOT	444	444	----

*SPECIALTY ITEM