

ENGINEER FIELD OFFICE TYPE A	CAL MO
77+40 TO 82+45	6
TOTAL	6

MOBILIZATION	L SUM
77+40 TO 82+45	1
TOTAL	1

TRAFFIC CONTROL AND PROTECTION STANDARD 701321	EACH
77+40 TO 82+45	1
TOTAL	1

TRAFFIC CONTROL AND PROTECTION STANDARD 701306	L SUM
77+40 TO 82+45	1
TOTAL	1

TRAFFIC CONTROL AND PROTECTION STANDARD 701326	L SUM
77+40 TO 82+45	1
TOTAL	1

CONSTRUCTION LAYOUT	L SUM
79+24 TO 80+59	1
TOTAL	1

TRAFFIC CONTROL SURVEILLANCE	CAL DA
77+40 TO 82+45	15
TOTAL	15

TEMPORARY BRIDGE TRAFFIC SIGNAL (SPECIAL)	EACH
77+40 TO 82+45	1
TOTAL	1

MOWING	UNIT
77+40 TO 82+45	10
TOTAL	10

LOCATION	TEMPORARY EROSION CONTROL SEEDING	TEMPORARY DITCH CHECK	PERIMETER EROSION BARRIER
STA TO STA	POUND	FOOT	FOOT
77+40 TO 82+45	200	300	400
TOTALS	200	300	400

SCHEDULE OF QUANTITIES

FILE NAME = 68662.dgn	USER NAME = coning	DESIGNED -	REVISED -
		DRAWN -	REVISED -
		CHECKED -	REVISED -
		DATE -	REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

IL 9  
Schedule of Quantities

F.A.P. RTE. 688	SECTION (118B)BR-1	COUNTY McDonough	TOTAL SHEETS 8	SHEET NO. 8
CONTRACT NO. 68662				ILLINOIS FED. AID PROJECT