

SUMMARY OF QUANTITIES

**80% FED.
20% STATE**

PAY ITEM NUMBER	PAY ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	ROADWAY	STRUCTURE
			CONSTRUCTION CODE	0004	0011
20200100	EARTH EXCAVATION	CU YD	330	330	
20200500	EARTH EXCAVATION (WIDENING)	CU YD	80	80	
20300100	CHANNEL EXCAVATION	CU YD	341	341	
20400800	FURNISHED EXCAVATION	CU YD	675	675	
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	2818	2818	
* 25000210	SEEDING, CLASS 2A	ACRE	0.75	0.75	
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	53	53	
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	53	53	
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	53	53	
* 25100115	MULCH, METHOD 2	ACRE	6.75	6.75	
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	621	621	
28000305	TEMPORARY DITCH CHECKS	FOOT	45	45	
28000400	PERIMETER EROSION BARRIER	FOOT	850	850	
28000500	INLET AND PIPE PROTECTION	EACH	1	1	
28100109	STONE RIPRAP, CLASS A5	SQ YD	1113	150	963
28200200	FILTER FABRIC	SQ YD	1349	150	1199
35600716	HOT-MIX ASPHALT BASE COURSE WIDENING, 10"	SQ YD	309	309	
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	95	95	
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	10	10	
40600215	POLYMERIZED BITUMINOUS MATERIALS (PRIME COAT)	TON	1	1	
40600300	AGGREGATE (PRIME COAT)	TON	240	240	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	174	174	
40600990	TEMPORARY RAMP	SQ YD	96	96	
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	110	110	
42001430	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	SQ YD	46	46	
44000100	PAVEMENT REMOVAL	SQ YD	177	177	
44000151	HOT-MIX ASPHALT SURFACE REMOVAL, 1/2"	SQ YD	1211	1211	
48101500	AGGREGATE SHOULDERS, TYPE B 6"	SQ YD	54	54	
48203100	HOT-MIX ASPHALT SHOULDERS	TON	47	47	
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1		1

***SPECIALTY ITEM**

LAST SAVED = 12/16/2010
 PEN TABLE = V8-Half.tbl
 PLOT DRIVER = PLOTDRIVER-BLack-Half.plt

FILE NAME =	USER NAME = beriechmann	DESIGNED -	REVISED -
h:\08044\1194\cad\1\plans\0468693-5ht-500.dgn		DRAWN -	REVISED -
		CHECKED -	REVISED -
		DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**HORNER &
SHERIN, INC.**
ENGINEERS

SUMMARY OF QUANTITIES

SCALE: 1" = 20' SHEET NO. 1 OF 3 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
534	109BR-1	HENDERSON	56	3
IL 94/116 OVER ELLISON CREEK		CONTRACT NO. 68693		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		