

**SUMMARY OF QUANTITIES**

**80% FED.  
20% STATE**

PAY ITEM NUMBER	PAY ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	ROADWAY	STRUCTURE
			CONSTRUCTION CODE	0004	0011
50105220	PIPE CULVERT REMOVAL	FOOT	21	21	
50200100	STRUCTURE EXCAVATION	CU YD	275		275
50300100	FLOOR DRAINS	EACH	14		14
50300225	CONCRETE STRUCTURES	CU YD	161.9		161.9
50300255	CONCRETE SUPERSTRUCTURE	CU YD	394.3		394.3
50300260	BRIDGE DECK GROOVING	SQ YD	570		570
50300280	CONCRETE ENCASEMENT	CU YD	8.5		8.5
50300300	PROTECTIVE COAT	SQ YD	734		734
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	127300		127300
50800515	BAR SPLICERS	EACH	511		511
51200958	FURNISHING METAL SHELL PILES 14" X 0.250"	FOOT	1725		1725
51202305	DRIVING PILES	FOOT	1725		1725
51203200	TEST PILE METAL SHELLS	EACH	4		4
51204650	PILE SHOES	EACH	32		32
51500100	NAME PLATES	EACH	1		1
54213453	END SECTIONS 18"	EACH	2	2	
542C0223	PIPE CULVERTS, CLASS C, TYPE 1 18"	FOOT	89	89	
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	48		48
* 63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	287.5	287.5	
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	4	4	
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	2	2	
* 63100169	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) FLARED	EACH	2	2	
63200310	GUARDRAIL REMOVAL	FOOT	454	454	
66600105	FURNISHING AND ERECTING RIGHT OF WAY MARKERS	EACH	11	11	
66700205	PERMANENT SURVEY MARKERS, TYPE 1	EACH	1	1	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	10	10	
67100100	MOBILIZATION	L SUM	1	1	
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	1	1	
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1	
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	1	

\*SPECIALTY ITEM

LAST SAVED = 12/16/2010  
PEN TABLE = V8-HotF.tbl  
PLOT DRIVER = TRV8PLOT.DOC

FILE NAME =	USER NAME = bartechmann	DESIGNED -	REVISED -
1:\00844\1194\oad\1\plans\0468693-Sht	500.dgn	DRAWN -	REVISED -
	PLOT SCALE = 40.0018 "/ IN.	CHECKED -	REVISED -
	PLOT DATE = 12/16/2010 10:20:28 AM	DATE -	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**HORNER &  
SHIRIN, INC.**  
ENGINEERS

**SUMMARY OF QUANTITIES**

SCALE: 1" = 20' SHEET NO. 2 OF 3 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
534	109BR-1	HENDERSON	56	4
IL 94/116 OVER ELLISON CREEK			CONTRACT NO. 68693	
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		